



**Call Order: 001 Proposal: E3R51**

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (22023625201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,356.000
	0120- 1-	REGULAR EXCAVATION	CY	370.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	539.500
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	2,360.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,062.000
	0327- 70- 2	MILLING EXIST ASPH PAVT, 3 1/2" AVG DEPTH	SY	44,323.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	65,476.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	15,133.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	4,991.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	12,201.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	6.800
	0425- 1-315	INLETS, CURB TYPE P-1, PARTIAL	EA	2.000
	0425- 1-345	INLETS, CURB, TYPE P-4, PARTIAL	EA	3.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	4.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	46.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	8.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	17.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,778.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,145.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	23.000
	0521- 5- 11	CONCRETE TRAFFIC RAILING- BRIDGE, RETROFIT-POST & BEAM RAILING	EA	2.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,537.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,063.000
	0527- 2-	DETECTABLE WARNINGS	SF	638.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	169.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	3.000
	0536- 8- 11	APPROACH TRANSITION TO RIGID BARRIER CONNECTION, FURNISH & INSTALL	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	122.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,360.000
	0639- 7-103	ELECTRICAL POWER SERVICE- RELOCATE POWER FOR NAVIGATIONAL LIGHTS, PROJECT 220236-2-52-01	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.785
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.177
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,960.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	227.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	947.000

**Call Order: 001 Proposal: E3R51**

ALT	Item	Description	Unit	Quantity
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	5.285
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.012
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	162.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.483
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.266
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22023625201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	37.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	5.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	15.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	7.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	89.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	16.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	1,063.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (22023625201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.177
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,960.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	227.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	947.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	2.012
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	162.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.266
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,858.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	62.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	62.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	7.785
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	5.285
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.483
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	912.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,795.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	6.000

**Call Order: 001 Proposal: E3R51**

ALT	Item	Description	Unit	Quantity
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	52.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	24.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	12.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	14.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	10.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	11.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	48.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	49.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	34.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	10.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	6.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	3.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	17.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	14.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	4.000