

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	03181011	Call Order: 005	Proposal: E3S18	District: 03
Counties:	WALTON			
Road Name:	PONCE DE LEON MAINTENANCE - SLOPE REPAIR SR 20			
Limits:	Midpoint			
Project(s):	42214327233(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	45	
Total Bridge Length:	0.000 Miles	Letting Date:	10/11/18	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 DAYS	
Proposal Budget Estimate:	\$480,000.00			

Please read the full advertisement

Description:

The Improvements under this Site-Specific Contract consist of providing all personnel, equipment and materials necessary to Repair Slope Erosion along the south side of State Road 20 in Walton County, from Milepost 2.111 (just west of Mohawk Avenue) to Milepost 2.324. This will require removal and replacement of approximately 20 feet of 24-inch Round Concrete Pipe and one 24-inch Mitered End Section, as well as the placement of Bank & Shore Rip Rap Rubble from a point beginning approximately 15 feet from the outside edge line of the eastbound travel lane, and extending approximately 20 feet toward the toe of slope. Work will require placement of miscellaneous asphalt for guardrail pad. Periodic lane closures will be allowed between the hours of 8:00 AM and 3:00 PM with prior approval of Engineer. Removal and replacement of guardrail may be necessary to accomplish placement of the rubble. All guardrail to be replaced at the end of each work day. Mobilization, Maintenance of Traffic and removal & replacement of guardrail shall be incidental to the bid items.

**Call Order: 005 Proposal: E3S18**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MANUAL) (TN)</b>				
	0104- 10- 3	SEDIMENT BARRIER	LF	950.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,000.000
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3,200.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	10.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	43.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	20.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,150.000
	0530- 74-	BEDDING STONE	TN	710.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	900.000