

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03181011 Call Order: 007 Proposal: E3S20-R0 District:03
 Counties: GADSDEN, LEON
 Road Name: MIDWAY MAINTENANCE - DESILTING AND VIDEO
 Limits: Midpoint
 Project(s): 42215127208(*) Federal Aid No: N/A
 Total Roadway Length: 0.000 Miles Contract Days: Thru 12/31/2019
 Total Bridge Length: 0.000 Miles Letting Date: 10/11/18
 Total Proposal Length: 0.000 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 DAYS
 Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

The Improvements under this Work Document-driven Contract consists of desilting, mapping, and submission of recorded video and written inspection reports of drainage pipes, inlets, manholes and concrete box culverts on State Roads in Gadsden and Leon Counties. Daytime lane closures are not permitted. Other improvements may include dewatering, debris removal, providing vehicular and pedestrian Maintenance of Traffic (MOT), sodding and watering disturbed areas. Maintenance of Traffic and Mobilization are incidental to the pay items listed.

This contract has a budgetary ceiling of \$500,000.00.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Call Order: 007 Proposal: E3S20-R0

| ALT | Item | Description | Unit | Quantity |
|--|-------------|---|------|------------|
| Section 0001 CLEAN DRAINAGE STRUCTURES (LF) | | | | |
| | 0430- 94- 1 | DESILTING PIPE, 0 - 24" | LF | 41,100.000 |
| | 0430- 94- 2 | DESILTING PIPE, 25 - 36" | LF | 17,125.000 |
| | 0430- 94- 3 | DESILTING PIPE, 37 - 48" | LF | 6,850.000 |
| | 0430- 94- 4 | DESILTING PIPE, 49 - 60" | LF | 2,055.000 |
| | 0430- 94- 5 | DESILTING PIPE, 61" OR GREATER | LF | 1,370.000 |
| | 0430-950- | DESILTING CONCRETE BOX CULVERT | CY | 320.000 |
| | E425- 73- 1 | CLEANING MANHOLES AND INLETS (MECHANICAL) | EA | 1,770.000 |
| | E432- 4- | STORM SEWER INSPECTION (VIDEO CAMERA) | LF | 68,500.000 |