

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 03181108 Call Order: 006 Proposal: E3S25 District:03

Counties: HOLMES

Road Name: PONCE DE LEON MAINTENANCE - DITCH RESHAPING

Limits: Midpoint

Project(s): 42214327234(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	11/08/18
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: \$120,000.00

Please read the full advertisement

Description:

The Improvements under this Site-Specific Contract consist of reshaping ditches and reworking shoulders along State Road 2 in Holmes County at designated locations, from State Road 81 (Mile Post 6.711) to Holmes County Road 171 (Mile Post 33.609), as shown in the Appendices. These ditches are non-typical and should be re-graded to +/- 3 inches of the original flow line to create a free and unobstructed flow of drainage water. For the purposes of this contract, the original flow line is considered to be the linear projection along the ditch bottom between the invert elevations of immediately adjacent drainage structures. Spoil material removed from ditches will be used for reworking shoulders, all remaining material shall be relocated to FDOT storage pit in Argyle or at 0.10 miles west of Wrights Creek Road on SR 2. Mobilization and Maintenance of Traffic shall be incidental to the bid items.

Call Order: 006 Proposal: E3S25

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0104- 10- 3	SEDIMENT BARRIER	LF	750.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	100.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	12,000.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	12,207.000
	E577- 70-	SHOULDER REWORK	SY	10,850.000