

Call Order: 005 Proposal: E3S13

ALT	Item	Description	Unit	Quantity
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	4,500.000
	0102-911- 3	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK, OTHER	SF	2,700.000
	0102-912- 1	PAVT MARKING REMOVABLE TAPE, YELLOW, SKIP	LF	1,500.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	4,500.000
	0102-912- 3	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, OTHER	SF	2,700.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,000.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	30.000
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	10.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	960.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	15.000
	0120- 1-	REGULAR EXCAVATION	CY	10,000.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	9,600.000
	0120- 4-	SUBSOIL EXCAVATION	CY	9,600.000
	0160- 4-	TYPE B STABILIZATION	SY	45,000.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	15,000.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	12,000.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	22,500.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	2,700.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	12,000.000
	0286- 1-	TURNOUT CONSTRUCTION	SY	360.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	48,000.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	48,000.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	48,000.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	48,000.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	48,000.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	9,000.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,800.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	900.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	900.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	1,200.000
	0337- 7- 26	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, HIGH POLYMER	TN	1,200.000
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22	TN	1,200.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	1,200.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	1,200.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	1,200.000
	0337- 7- 90	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, HIGH POLYMER	TN	1,200.000
	0337- 7- 91	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, HIGH POLYMER	TN	1,200.000
	0337- 7- 92	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, HIGH POLYMER	TN	1,200.000
	0337- 7- 93	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, HIGH POLYMER	TN	1,200.000

Call Order: 005 Proposal: E3S13

ALT	Item	Description	Unit	Quantity
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	45.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	65.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	18.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	9.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	9.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	9.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	6.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	6.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	6.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	6.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	6.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	6.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	6.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	6.000
	0425- 3- 61	JUNCTION BOXES, J-7, <10'	EA	6.000
	0425- 4-	INLETS, ADJUST	EA	6.000
	0425- 5-	MANHOLE, ADJUST	EA	6.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	330.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	330.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	330.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	330.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	330.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	330.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	330.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	330.000
	0430-612-133	U-ENDWALL, GRATE, STD 261, 1:4 SLOPE, 30" PIPE	EA	3.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	18.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	6.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	60.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	6.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	200.000
	0440- 1- 20	UNDERDRAIN, TYPE II	LF	6.000
	0440- 70-	UNDERDRAIN INSPECTION BOX	EA	6.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	6.000
	0515- 2-111	PEDESTRIAN / BICYCLE RAILING, NS, 42" TYPE 1	LF	120.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	675.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,500.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	1,000.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	800.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	1,000.000
	0520- 5- 42	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	LF	800.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	750.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	200.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	300.000

Call Order: 005 Proposal: E3S13

ALT	Item	Description	Unit	Quantity
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	250.000
	0527- 2-	DETECTABLE WARNINGS	SF	160.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	75.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	600.000
	0536- 73-	GUARDRAIL REMOVAL	LF	600.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	12.000
	0544- 75- 1	CRASH CUSHION	EA	5.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	10.000
	0546- 72- 2	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL	GM	10.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	10.000
	0570- 1- 1	PERFORMANCE TURF	SY	15,000.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	15,000.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	60.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	6.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	80.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	80.000
	0700- 2- 11	MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	12.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	12.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	12.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	12.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	12.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	6.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	6.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	6.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	6.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	6.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	6.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	6.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	6.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	6.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	6.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	6.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	6.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	6.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	6.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	6.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	6.000
	0700- 4-512	OVERHEAD STATIC SIGN STRUCTURE, RELOCATE, CANTILEVER, 21-30 FT	EA	2.000
	0701- 17-101	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, WHITE, SOLID,6"	GM	9.000
	0701- 17-201	PROFILED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, YELLOW, SOLID,6"	GM	9.000

Call Order: 005 Proposal: E3S13

ALT	Item	Description	Unit	Quantity
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	9.000
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	6.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	12.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	65.000
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	2,200.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	9.000
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	9.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,500.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	300.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,500.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.750
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	8.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	24.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	100.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	200.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	12.000
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	800.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	100.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	5.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	720.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	300.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,200.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	8.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	24.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	100.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	200.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	800.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	4.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	1,400.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,400.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	12.000

Call Order: 005 Proposal: E3S13

ALT	Item	Description	Unit	Quantity
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	24.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	12.000
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	9.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.000
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.500
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	12.000
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	9.000
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.750
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	9.000
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	9.000
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.750
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	9.000
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	9.000
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.750
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	1,000.000
Section 0003 Lighting				
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,000.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	30.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,500.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,800.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	600.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	8.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	12.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	18.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	15.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	20.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	20.000
	0646- 1- 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	20.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	20.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	2.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	60.000
	0650- 1- 35	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 2-4 WAYS	AS	30.000

Call Order: 005 Proposal: E3S13

ALT	Item	Description	Unit	Quantity
	0650- 1- 36	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 4 SECTION, 1 WAY	AS	30.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	16.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	30.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	30.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	30.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	18.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	18.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	18.000
	0660- 4- 42	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE ABOVE GROUND EQUIPMENT	EA	20.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	30.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	30.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	30.000