Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 03190416 Call Order: 001 Proposal: E3S63 District:03

Counties: GADSDEN, JEFFERSON, LEON

Road Name: SR 8 (I-10) Limits: 50001000

Project(s): 4452481G201(*) Federal Aid No: E191083E

 Project(s):
 4452482G201
 Federal Aid No: N/A

 Project(s):
 4452492G201
 Federal Aid No: N/A

 Project(s):
 4452502G201
 Federal Aid No: N/A

Total Roadway Length: 217.406 Miles Contract Days: 180

Total Bridge Length: 0.000 Miles Letting Date: 04/16/19

Total Proposal Length: 217.406 Miles Contract Execution Days: 5

Special Start Date: N/A

Aquis/Flexible Start Time: 60 Days Acquis. Time

Proposal Budget Estimate: \$1,625,895.00

Please read the full advertisement

Description:

This Permanent Repair Contract shall consist of repair/replacement of damaged Wildlife Fence along the SR-8 (I-10) corridor in Gadsden, Leon, and Jefferson Counties. Additionally, any fence repair that is necessary at FDOT rest areas and weigh-in motion facilities along SR 8 (I-10) shall be included.

Fence installation shall include resetting or removal/replacement of any fence damaged by Hurricane Michael within the Counties specified in this Contract. Location of Damage Sites can be found in the attached DDIR Log and within the GIS Emergency Fence Viewer located at the following web address:

https://arcg.is/1u0WeP . The preliminary quantities reflected within the GIS viewer and DDIR Log spreadsheet for each damaged location have been provided for informational purposes only. Bids shall be based on the quantities reflected within the Bid Sheet. Additional damaged areas noted in the field shall be repaired at the direction of the Engineer. Each Damage Site is an approximate location and is subject to variability of quantified damage length and location accuracy.

All work shall be in accordance with the January 2019 Standard Specifications for Road and Bridge Construction, the FY 2018-19 Standard Plans for Road and Bridge Construction, and the Wildlife Fence Special Details provided within this scope.

Due to environmentally sensitive areas the Contractor will not be permitted to stage or store equipment and materials within the R/W at the following locations:

- 1) From 0.5 miles west of MM 164 to MM 164 (Gadsden County Straight Line Diagram Milepost 3.764-4.264).
- 2) From MM 197 to 0.5 miles east of MM 197 (Leon County Straight Line Diagram Milepost 3.887-4.387).
- 3) From 0.5 miles west of MM 218 to MM 218 (Jefferson County Straight Line Diagram Milepost 2.179-2.679).

The work area shall be limited to only that which is required to perform fencing operations. Any fence removed solely to provide access for repairs shall be considered incidental and replaced by the Contractor at no additional expense to the Department. Daytime lane closures shall be coordinated with the local FDOT Operations Center.

The Contractor shall coordinate with any utility owners and exercise care when performing work activities around buried or exposed utilities within the project limits.

There will be no fuel adjustments to this contract.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

FHWA 1273 and Davis Bacon Wage Rates are applicable for this Contract

Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Call Order: 001 Proposal: E3S63				
ALT	Item	Description	Unit	Quantity
Section	0001 Roadway			
	0101- 1-	MOBILIZATION (4452481G201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (4452481G201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (4452481G201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (4452482G201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (4452492G201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (4452502G201)	LS	1.000
	0550- 10-110	FENCING, TYPE A, 0.0-5.0', STANDARD	LF	400.000
	0550- 10-149	FENCING, TYPE A, 7.1-8.0', SPECIAL FEATURES	LF	85,782.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	20.000
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT	LF	265.000