

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

|                        |                |                            |                 |             |
|------------------------|----------------|----------------------------|-----------------|-------------|
| Letting:               | 03190110       | Call Order: 001            | Proposal: E3R52 | District:03 |
| Counties:              | ESCAMBIA       |                            |                 |             |
| Road Name:             | SR 30          |                            |                 |             |
| Limits:                | 48280000       |                            |                 |             |
| Project(s):            | 43627225201(*) | Federal Aid No:            | N/A             |             |
| Total Roadway Length:  | 1.977 Miles    | Contract Days:             | 180             |             |
| Total Bridge Length:   | 0.000 Miles    | Letting Date:              | 01/10/19        |             |
| Total Proposal Length: | 1.977 Miles    | Contract Execution Days:   | 10              |             |
|                        |                | Special Start Date:        | N/A             |             |
|                        |                | Aquis/Flexible Start Time: | 15 days         |             |

Proposal Budget Estimate: \$2,002,649.00

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of milling and resurfacing of SR 30 (US 98) from SR 298 (Lillian Highway) to West of SR 173 (Blue Angel Parkway) in Escambia County, more specifically from MP 0.293 to MP 1.899. Improvements also include widening for turn lane improvements, drainage improvements, guardrail improvements, and signing and pavement markings.

**Call Order: 001 Proposal: E3R52**

| ALT                         | Item        | Description  | Unit | Quantity   |
|-----------------------------|-------------|--|------|------------|
| <b>Section 0001 Roadway</b> |             |  |      |            |
|                             | 0101- 1-    | MOBILIZATION (43627225201)                             | LS   | 1.000      |
|                             | 0102- 1-    | MAINTENANCE OF TRAFFIC (43627225201)                   | LS   | 1.000      |
|                             | 0102- 3-    | COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE | CY   | 171.400    |
|                             | 0102- 60-   | WORK ZONE SIGN   | ED   | 9,170.000  |
|                             | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED   | 37,876.000 |
|                             | 0102- 78-   | TEMPORARY RETROREFLECTIVE PAVEMENT MARKER              | EA   | 2,428.000  |
|                             | 0102- 99-   | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY            | ED   | 374.000    |
|                             | 0104- 10- 3 | SEDIMENT BARRIER                                       | LF   | 5,041.000  |
|                             | 0104- 11-   | FLOATING TURBIDITY BARRIER                             | LF   | 260.000    |
|                             | 0104- 12-   | STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC         | LF   | 104.000    |
|                             | 0107- 1-    | LITTER REMOVAL   | AC   | 97.450     |
|                             | 0107- 2-    | MOWING   | AC   | 86.260     |
|                             | 0110- 1- 1  | CLEARING & GRUBBING (43627225201)                      | LS   | 1.000      |
|                             | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE                           | SY   | 177.000    |
|                             | 0120- 1-    | REGULAR EXCAVATION                                     | CY   | 2,907.300  |
|                             | 0120- 2- 2  | BORROW EXCAVATION, TRUCK MEASURE                       | CY   | 1,543.800  |
|                             | 0162- 1- 11 | PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"             | SY   | 6,664.000  |
|                             | 0285-702-   | OPTIONAL BASE, BASE GROUP 02                           | SY   | 157.000    |
|                             | 0285-708-   | OPTIONAL BASE, BASE GROUP 08                           | SY   | 1,175.000  |
|                             | 0285-711-   | OPTIONAL BASE, BASE GROUP 11                           | SY   | 4,708.000  |
|                             | 0286- 1-    | TURNOUT CONSTRUCTION                                   | SY   | 164.000    |
|                             | 0327- 70- 6 | MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH              | SY   | 23,195.000 |
|                             | 0327- 70- 8 | MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH              | SY   | 2,350.000  |

**Call Order: 001 Proposal: E3R52**

| ALT                         | Item         | Description  | Unit | Quantity   |
|-----------------------------|--------------|--|------|------------|
|                             | 0327- 70- 19 | MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH  | SY   | 129.000    |
|                             | 0334- 1- 52  | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22   | TN   | 2,753.300  |
|                             | 0337- 7- 80  | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22                                  | TN   | 2,753.500  |
|                             | 0400- 1- 2   | CONCRETE CLASS I, ENDWALLS   | CY   | 14.800     |
|                             | 0430-174-124 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD  | LF   | 143.000    |
|                             | 0430-175-136 | PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD   | LF   | 80.000     |
|                             | 0430-175-224 | PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE-ELIP/ARCH, 24"S/CD                                | LF   | 340.000    |
|                             | 0430-611-229 | U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:3 SLOPE, 24"PIPE                                  | EA   | 1.000      |
|                             | 0430-982-138 | MITERED END SECTION, OPTIONAL ROUND, 36" CD  | EA   | 4.000      |
|                             | 0430-984-129 | MITERED END SECTION, OPTIONAL ROUND, 24" SD  | EA   | 3.000      |
|                             | 0430-984-629 | MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD   | EA   | 8.000      |
|                             | 0520- 1- 10  | CONCRETE CURB & GUTTER, TYPE F   | LF   | 24.000     |
|                             | 0520- 6-     | SHOULDER GUTTER- CONCRETE  | LF   | 434.000    |
|                             | 0524- 1- 1   | CONCRETE DITCH PAVT, NON REINFORCED, 3"  | SY   | 166.000    |
|                             | 0530- 3- 4   | RIPRAP, RUBBLE, F&I, DITCH LINING  | TN   | 42.000     |
|                             | 0536- 1- 1   | GUARDRAIL -ROADWAY, GENERAL TL-3   | LF   | 413.000    |
|                             | 0536- 7- 1   | SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK<br>CONDITION- TIMBER OR STEEL                | EA   | 67.000     |
|                             | 0536- 7- 3   | SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT   | EA   | 1.000      |
|                             | 0536- 85- 24 | GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL  | EA   | 2.000      |
|                             | 0536- 85- 25 | GUARDRAIL END TREATMENT- TRAILING ANCHORAGE TYPE II  | EA   | 2.000      |
|                             | 0570- 1- 2   | PERFORMANCE TURF, SOD  | SY   | 10,577.000 |
|                             | 0571- 1- 11  | PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1   | SY   | 165.000    |
|                             | 0695- 7-600  | TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET                                       | EA   | 1.000      |
|                             | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"  | GM   | 7.426      |
|                             | 0710- 11-124 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR<br>DIAGONAL OR CHEVRON, 18"              | LF   | 328.000    |
|                             | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR<br>STOP LINE OR CROSSWALK, 24"           | LF   | 257.000    |
|                             | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED<br>GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM   | 1.668      |
|                             | 0710- 11-160 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR<br>SYMBOL                               | EA   | 23.000     |
|                             | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS   | EA   | 39.000     |
|                             | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"   | GM   | 6.557      |
|                             | 0710- 11-224 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR<br>DIAGONAL OR CHEVRON, 18"             | LF   | 1,027.000  |
|                             | 0710- 11-231 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"  | GM   | 2.263      |
|                             | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43627225201)   | LS   | 1.000      |
| <b>Section 0002 Signing</b> |              |  |      |            |
|                             | 0700- 1- 11  | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF  | AS   | 11.000     |
|                             | 0700- 1- 60  | SINGLE POST SIGN, REMOVE   | AS   | 6.000      |
|                             | 0701- 18-101 | PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES,<br>WHITE, SOLID, 6"                        | GM   | 1.927      |
|                             | 0701- 18-201 | PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES,<br>YELLOW, SOLID, 6"                       | GM   | 1.228      |

**Call Order: 001 Proposal: E3R52**

| ALT | Item         | Description  | Unit | Quantity |
|-----|--------------|--|------|----------|
|     | 0705- 10- 2  | OBJECT MARKER, TYPE 2  | EA   | 5.000    |
|     | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43627225201)                       | LS   | 1.000    |
|     | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS        | LF   | 164.000  |
|     | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK       | LF   | 165.000  |
|     | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" | GM   | 0.450    |
|     | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW  | EA   | 21.000   |
|     | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON          | LF   | 513.000  |
|     | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE                                     | EA   | 10.000   |
|     | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW                                       | EA   | 10.000   |
|     | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"                     | GM   | 1.585    |
|     | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"                    | GM   | 1.662    |
|     | 0711- 16-231 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"                     | GM   | 0.566    |