

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03190905	Call Order: 002	Proposal: E3S95	District:03
Counties:	BAY			
Road Name:	- EMERGENCY OPERATIONS			
Limits:	46010100			
Project(s):	44501845201	Federal Aid No:	N/A	
Project(s):	4450184H201(*)	Federal Aid No:	E191129E	
Total Roadway Length:	1.366 Miles	Contract Days:	90	
Total Bridge Length:	0.000 Miles	Letting Date:	09/05/19	
Total Proposal Length:	1.366 Miles	Contract Execution Days:	5	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	

Proposal Budget Estimate: \$689,202.00

Please read the full advertisement

Description:

The Improvements under this Contract FPID 445018-4-H2-01 consist of permanent replacement of all aesthetic (pier up lights), maintenance and navigation lights located on the underside of the bridge, piers and pier footings with new LED light fixtures on SR 30 (US 98) Hathaway Bridge, No. 460112 & 460113 in Bay County. Also included will be removal and permanent replacement of all surface mounted conduit associated with bridge lighting and installation of new surface mounted conduit where required for new conductors. Permanent replacement of conductor wiring from the new fixtures up to junction boxes located within (inside) the segment box of the Bridge No. 460113 above (westbound SR 30) above.

Under FPID 445018-4-52-01, work includes the addition of supplemental pipe hangers to support two - 2 - inch diameter roof mounted PVC conduits located inside the segmental box of the Bridged No. 460113 (westbound SR 30) for the entire length of the bridge. The details for hangers are included in the plans.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.
FHWA 1273 AND DAVIS BACON WAGE RATES ARE APPLICABLE FOR THIS CONTRACT.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 002 Proposal: E3S95

ALT	Item	Description	Unit	Quantity
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44501845201)	LS	1.000
	0101- 1-	MOBILIZATION (4450184H201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44501845201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (4450184H201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	270.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,980.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	990.000
	0104- 10- 3	SEDIMENT BARRIER	LF	310.000
	0460- 98- 2	PIPE HANGER, STAINLESS	EA	565.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	400.000
	0630- 2- 65	CONDUIT, REMOVE, BRIDGE MOUNT	LF	400.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	23.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	4,685.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,230.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	5,215.000
	0715- 11- 21	LUMINAIRE- PIER LIGHT, F&I, PROJECT 445018-4-H2-01	EA	26.000
	0715- 11- 22	LUMINAIRE- CHANNEL NAVIGATION, F&I, PROJECT 445018-4-H2-01	EA	4.000
	0715- 11- 23	LUMINAIRE- MAINTENANCE LIGHTS, F&I, PROJECT 445018-4-H2-01	EA	9.000
	0715- 21- 5	LUMINAIRE, PIER LIGHTS, REMOVE	EA	19.000
	0715- 21- 6	LUMINAIRE, NAVIGATION LIGHTS, REMOVE	EA	4.000
	0715- 21- 7	LUMINAIRE, MAINTENANCE LIGHTS, REMOVE	EA	9.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44501845201)	LS	1.000