



Vendor Ranking

Letting: 04250404 April 04, 2025 10:30 AM **Call Order:** 001 **Contract:** E4X35
District: District 4 **Counties:** BROWARD **Fed Aid No:** N/A
Contract Time: 397 AVAILABLE DAYS **Project(s):** 44925715201 (*)
Contract Desc: SR-842/LAS OLAS BLVD OVER ICWW - BRWD CTY - BRG-REPAIR/REHAB

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	SEACOAST INCORPORATED	Responsive	Winning bid	\$14,053,215.67	100.00%
2	GLF CONSTRUCTION CORPORATION	Responsive	Non-Winning Bid	\$14,479,476.86	103.03%
3	PCL CIVIL CONSTRUCTORS, INC.	Responsive	Non-Winning Bid	\$18,177,978.14	129.35%
4	SOUTHERN ROAD & BRIDGE, LLC	Responsive	Non-Winning Bid	\$20,697,651.09	147.28%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

NOTICE TO INTENT TO AWARD WAS POSTED: **BEGIN DATE:** 04/29/25 **BEGIN TIME:** 10:30 AM
END DATE: 05/02/25 **END TIME:** 10:30 AM



Tabulation of Bids

Letting: 04250404 April 04, 2025 **Call Order:** 001 **Contract:** E4X35
District: District 4 **Counties:** BROWARD **Fed Aid No:** N/A
Contract Time: 397 AVAILABLE DAYS **Project(s):** 44925715201 (*)

Contract Descr: SR-842/LAS OLAS BLVD OVER ICWW - BRWD CTY - BRG-REPAIR/REHAB

The Improvements under this Contract consist of, but are not limited to, MOT (standard, traffic control officer, pedestrian LCD, Arrow Board, PCMS, signalization, traffic detection, barricade), monitor structures (inspection, settlement), Bridge Number 860018 (removal, expansion joint, moveable bridge rehabilitation/repair/maintenance/operator, control house renovation, rivets/bolts), structural steel (bascule leaves, coating), bridge fender system (removal, polymeric install), concrete (cleaning/sealing surfaces, curb and gutter, sidewalk, driveways), asphalt (milling, resurfacing), pavement markings (removable tape, RPM, painted, thermoplastic), signage (single-column), conduit (directional bore), pull/splice box, traffic monitoring (sensor, inductive loop), and floating turbidity barrier along Las Olas Boulevard for 0.207 miles in the City of Fort Lauderdale, Broward County.

- PRE-QUALIFIED: Contractor must be pre-qualified.
- PERFORMANCE BOND: A Contract / Performance bond is required for this project.

MARINE GENERAL LIABILITY INSURANCE Marine General Liability Insurance as referenced in Section 7-13.5 of the FDOT Standard Specifications may be required if any work under this Contract is performed using vessel(s)*. Prior to the Contract execution, Contractor shall provide written certification to the Department if no vessel(s) will be used for the work. * Vessel: a watercraft or other artificial contrivance, whether motorized or non-motorized, used to perform some or all of the work, as well as any incidental work related to the project, which includes, but is not limited to, barges, dredges, mobile offshore drilling units, floating cranes, tugboats, ferries, and any watercraft used to transport construction workers, materials, or equipment at the project.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2024-25 (SECTION 7-13) FOR INSURANCE LIMITS.

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0005 0110 3 REMOVAL OF EXISTING STRUCTURES/BRIDGES 44925715201/Bridge ID 860018		(5336.000) SF (LS)	268,000.00000	268,000.00	270,000.00000	270,000.00	450,000.00000	450,000.00
0010 0110 71 1 BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL		384.000 LF	2,500.00000	960,000.00	1,200.00000	460,800.00	1,200.00000	460,800.00



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0015 0400143 CLEANING & COATING CONCRETE SURFACE, CLASS 5		55,415.000 SF	5.80000	321,407.00	2.80000	155,162.00	7.00000	387,905.00
0020 0413149 PENETRANT SEALER		7.000 GA	150.00000	1,050.00	180.00000	1,260.00	150.00000	1,050.00
0025 0413154 CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES		1,800.000 SF	10.00000	18,000.00	6.00000	10,800.00	9.00000	16,200.00
0030 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD		570.000 LF	25.00000	14,250.00	110.00000	62,700.00	75.00000	42,750.00
0035 0460 1 5 STRUCT STEEL - REHABILITATION, BASCULE LEAVES		68,425.000 LB	15.00000	1,026,375.00	12.00000	821,100.00	16.00000	1,094,800.00
0040 0460 81 RIVETS - HIGH STRENGTH BOLTS, REPLACEMENT		30.000 EA	250.00000	7,500.00	135.00000	4,050.00	325.00000	9,750.00
0045 0465 2105 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, F&I SPAN LOCKS		2.000 AS	230,000.00000	460,000.00	625,000.00000	1,250,000.00	500,000.00000	1,000,000.00



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0050 0465 2401 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, RECONDITION, SPEED REDUCER & GEAR TRAIN 44925715201/Bridge ID 860018		(1.000) LS	80,000.00000	80,000.00	126,200.00000	126,200.00	320,000.00000	320,000.00
0055 0465 2508 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, ADJUST/MODIFY, LIVE LOAD SHOES 44925715201/Bridge ID 860018		(1.000) LS	25,000.00000	25,000.00	37,700.00000	37,700.00	15,000.00000	15,000.00
0060 0465 2605 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, REMOVE & DISPOSE-CONTRACTOR OWNS, SPAN LOCKS		2.000 AS	25,000.00000	50,000.00	10,000.00000	20,000.00	20,000.00000	40,000.00
0065 0465 2608 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, REMOVE & DISPOSE-CONTRACTOR OWNS, LIVE LOAD SHOES 44925715201/Bridge ID 860018		(1.000) LS	1,000.00000	1,000.00	13,400.00000	13,400.00	15,000.00000	15,000.00
0070 0465 3 17 MOVABLE BRIDGE COUNTERWEIGHT, F&I, BALANCE BLOCKS		640.000 EA	130.00000	83,200.00	266.00000	170,240.00	400.00000	256,000.00
0075 0465 3 50 MOVABLE BRIDGE COUNTERWEIGHT, ADJUST		2.000 EA	15,000.00000	30,000.00	70,000.00000	140,000.00	115,000.00000	230,000.00



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0080 0465 20 MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR 44925715201/Bridge ID 860018		(397.000) DA (LS)	90,000.00000	90,000.00	140,000.00000	140,000.00	35,000.00000	35,000.00
0085 0465 21 MOVABLE BRIDGE OPERATOR		397.000 DA	1,000.00000	397,000.00	950.00000	377,150.00	1,100.00000	436,700.00
0090 0465 71 3 MOVABLE BRIDGE FUNCTIONAL CHECKOUT, PHASE C 44925715201/Bridge ID 860018		(1.000) LS	90,000.00000	90,000.00	200,000.00000	200,000.00	75,000.00000	75,000.00
0095 0471 3 3 POLYMERIC FENDER SYSTEM, 201-400 KIP-FT 44925715201/Bridge ID 860018		(1.000) LS	2,800,000.00000	2,800,000.00	2,400,000.00000	2,400,000.00	3,500,000.00000	3,500,000.00
0100 0505 2100 ALUMINUM DECK PANELS, FURNISH & INSTALL		5,303.000 SF	280.00000	1,484,840.00	310.00000	1,643,930.00	425.00000	2,253,775.00
0105 0508 4 MOVABLE BRIDGE ELECTRICAL EQUIPMENT, REHABILITATION 44925715201/Bridge ID 860018		(1.000) LS	849,000.00000	849,000.00	800,000.00000	800,000.00	1,200,000.00000	1,200,000.00
0110 0508 76 1 MOVABLE BRIDGE - REHAB, SPAN MOTORS & CONTROLLERS , F&I 44925715201/Bridge ID 860018		(1.000) LS	300,000.00000	300,000.00	93,395.00000	93,395.00	300,000.00000	300,000.00
0115 0508 76 4 MOVABLE BRIDGE - REHAB, SPAN MOTORS & CONTROLLERS , REMOVE 44925715201/Bridge ID 860018		(1.000) LS	2,500.00000	2,500.00	17,372.00000	17,372.00	5,000.00000	5,000.00



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0120 0508 77 1 MOVABLE BRIDGE- REHAB,PROGRAMMABLE LOGIC CONTROLLER F&I		1.000 EA	78,125.00000	78,125.00	55,083.00000	55,083.00	80,000.00000	80,000.00
0125 0508 78 1 MOVABLE BRIDGE-REHAB, LIMIT SWITCHES & TRANSDUCERS F&I 44925715201/Bridge ID 860018		(1.000) LS	36,000.00000	36,000.00	49,584.65000	49,584.65	105,000.00000	105,000.00
0130 0508 78 4 MOVABLE BRIDGE-REHAB, LIMIT SWITCHES & TRANSDUCERS REMOVE 44925715201/Bridge ID 860018		(1.000) LS	1,875.00000	1,875.00	6,461.76000	6,461.76	8,000.00000	8,000.00
0135 0508 79 1 MOVABLE BRIDGE-REHAB,CONTROL CONSOLE, F&I		1.000 EA	318,750.00000	318,750.00	940,025.00000	940,025.00	275,000.00000	275,000.00
0140 0508 79 4 MOVABLE BRIDGE-REHAB,CONTROL CONSOLE, REMOVE		1.000 EA	1,250.00000	1,250.00	3,230.75000	3,230.75	9,000.00000	9,000.00
0145 0508 80 1 MOVABLE BRIDGE-REHAB, BRAKE SYSTEM, F&I		4.000 EA	60,000.00000	240,000.00	24,565.00000	98,260.00	65,000.00000	260,000.00
0150 0508 80 4 MOVABLE BRIDGE-REHAB, BRAKE SYSTEM, REMOVE		4.000 EA	312.50000	1,250.00	795.00000	3,180.00	2,000.00000	8,000.00
0155 0508 82 5 MOVABLE BRIDGE-REHAB, CONTROL PANEL - MOTOR CONTROLLER, REPLACE		1.000 EA	62,400.00000	62,400.00	31,158.40000	31,158.40	75,000.00000	75,000.00



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0160 0508 83202 MOVABLE BRIDGE INTEGRATED DRIVE SYSTEM, REPLACE, 26-40 KW		4.000 EA	65,625.00000	262,500.00	62,250.00000	249,000.00	65,000.00000	260,000.00
0165 0512 1 1 MOVABLE BRIDGE-CONTROL HOUSE, RENOVATE 44925715201/Bridge ID 860018		(1.000) LS	260,000.00000	260,000.00	130,000.00000	130,000.00	225,000.00000	225,000.00
0170 0561 1 COATING EXISTING STRUCTURAL STEEL 44925715201/Bridge ID 860018		(374.000) TN (LS)	1,100,000.00000	1,100,000.00	1,250,000.00000	1,250,000.00	1,500,000.00000	1,500,000.00
0001 Structures Section Totals:				\$11,721,272.00		\$12,031,242.56		\$14,949,730.00

SECTION: 0002 Roadway								
0175 0101 1 MOBILIZATION 44925715201		(1.000) LS	1,200,000.00000	1,200,000.00	1,447,000.00000	1,447,000.00	1,800,000.00000	1,800,000.00
0180 0102 1 MAINTENANCE OF TRAFFIC 44925715201		(397.000) DA (LS)	600,000.00000	600,000.00	200,000.00000	200,000.00	500,000.00000	500,000.00
0185 0102 14 TRAFFIC CONTROL OFFICER		4,300.000 HR	10.00000	43,000.00	80.00000	344,000.00	85.00000	365,500.00
0190 0102 60 WORK ZONE SIGN		58,003.000 ED	0.24000	13,920.72	0.19000	11,020.57	0.20000	11,600.60



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway								
0195 0102 71 13 TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE		372.000 LF	60.00000	22,320.00	48.00000	17,856.00	64.50000	23,994.00
0200 0102 71 23 TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE		372.000 LF	25.00000	9,300.00	20.00000	7,440.00	28.50000	10,602.00
0205 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD		33,675.000 ED	0.12000	4,041.00	0.10000	3,367.50	0.15000	5,051.25
0210 0102 74 8 CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)		9,720.000 FD	0.06000	583.20	0.05000	486.00	0.10000	972.00
0215 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL		579.000 ED	6.00000	3,474.00	5.00000	2,895.00	5.50000	3,184.50
0220 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY		2,574.000 ED	11.00000	28,314.00	9.00000	23,166.00	10.00000	25,740.00
0225 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION		1,588.000 ED	30.00000	47,640.00	9.56000	15,181.28	26.75000	42,479.00
0230 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION		1,588.000 ED	30.00000	47,640.00	9.56000	15,181.28	26.75000	42,479.00



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway								
0235 0102115 TYPE III BARRICADE		7,595.000 ED	0.27000	2,050.65	0.23000	1,746.85	0.30000	2,278.50
0240 0102913 21 REMOVABLE TAPE, WHITE, SOLID 6"		0.095 GM	16,875.00000	1,603.13	14,210.00000	1,349.95	15,000.00000	1,425.00
0245 0102913 31 REMOVABLE TAPE, YELLOW, SOLID, 6"		0.530 GM	16,875.00000	8,943.75	13,500.00000	7,155.00	15,000.00000	7,950.00
0250 0104 11 FLOATING TURBIDITY BARRIER		1,000.000 LF	4.00000	4,000.00	40.00000	40,000.00	20.00000	20,000.00
0255 0107 1 LITTER REMOVAL		22.830 AC	500.00000	11,415.00	400.00000	9,132.00	325.00000	7,419.75
0260 0107 2 MOWING		0.940 AC	1,500.00000	1,410.00	12,000.00000	11,280.00	10,000.00000	9,400.00
0265 0108 1 MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING 44925715201		(1.000) LS	7,500.00000	7,500.00	20,000.00000	20,000.00	30,000.00000	30,000.00
0270 0327 70 12 MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH		691.000 SY	8.00000	5,528.00	10.00000	6,910.00	28.00000	19,348.00



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway								
0275 0337 7 82 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22		47.500 TN	185.00000	8,787.50	500.00000	23,750.00	1,120.00000	53,200.00
0280 0520 1 10 CONCRETE CURB & GUTTER, TYPE F		6.000 LF	150.00000	900.00	300.00000	1,800.00	930.00000	5,580.00
0285 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK		3.000 SY	150.00000	450.00	800.00000	2,400.00	1,825.00000	5,475.00
0290 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE		26.000 LF	43.75000	1,137.50	59.61000	1,549.86	35.00000	910.00
0295 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE		1.000 EA	1,500.00000	1,500.00	1,250.00000	1,250.00	1,150.00000	1,150.00
0300 0695 1 1 TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL		4.000 EA	3,750.00000	15,000.00	3,000.00000	12,000.00	2,950.00000	11,800.00
0305 0695 6 11 TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 1 LOOP		8.000 EA	4,375.00000	35,000.00	3,500.00000	28,000.00	3,500.00000	28,000.00
0310 0706 1 3 RAISED PAVEMENT MARKER, TYPE B		207.000 EA	8.75000	1,811.25	7.00000	1,449.00	5.00000	1,035.00



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway								
0315 0710 11101 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"		0.019 GM	3,125.00000	59.38	2,105.00000	40.00	2,650.00000	50.35
0320 0710 11201 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"		0.040 GM	3,125.00000	125.00	2,500.00000	100.00	2,650.00000	106.00
0325 0999 16 PARTNERING, DO NOT BID 44925715201		(1.000) LS	6,000.00000	6,000.00	6,000.00000	6,000.00	6,000.00000	6,000.00
0330 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 44925715201		(1.000) LS	129,909.59000	129,909.59	129,909.59000	129,909.59	129,909.59000	129,909.59
0002 Roadway Section Totals:				\$2,263,363.67		\$2,393,415.88		\$3,172,639.54

SECTION: 0003 Signing								
0335 0700 1111 SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF		1.000 EA	1,440.00000	1,440.00	1,200.00000	1,200.00	1,250.00000	1,250.00
0340 0700 1600 SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE		1.000 EA	120.00000	120.00	100.00000	100.00	150.00000	150.00
0345 0706 1 3 RAISED PAVEMENT MARKER, TYPE B		57.000 EA	8.75000	498.75	7.00000	399.00	5.00000	285.00



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing								
0350 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 44925715201		(1.000) LS	6,000.00000	6,000.00	5,000.00000	5,000.00	13,500.00000	13,500.00
0355 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS		17.000 LF	8.75000	148.75	7.00000	119.00	6.50000	110.50
0360 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAGE		1.000 EA	1,875.00000	1,875.00	1,500.00000	1,500.00	550.00000	550.00
0365 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"		0.024 GM	9,375.00000	225.00	6,250.00000	150.00	13,000.00000	312.00
0370 0711 16131 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP		0.034 GM	5,625.00000	191.25	3,975.00000	135.15	3,150.00000	107.10
0375 0711 16201 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"		0.034 GM	9,375.00000	318.75	6,630.00000	225.42	13,000.00000	442.00
0380 0713103101 PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES		0.422 GM	50,000.00000	21,100.00	39,825.00000	16,806.15	36,750.00000	15,508.50
0385 0713103181 PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES		0.415 GM	18,750.00000	7,781.25	14,900.00000	6,183.50	9,500.00000	3,942.50



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(1) SEACOAST INCORPORATED		(2) GLF CONSTRUCTION CORPORATION		(3) PCL CIVIL CONSTRUCTORS, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing								
0390 0713103201 PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES		0.422 GM	50,000.00000	21,100.00	39,850.00000	16,816.70	36,750.00000	15,508.50
0395 0713103381 PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES		0.415 GM	18,750.00000	7,781.25	14,900.00000	6,183.50	9,500.00000	3,942.50
0003 Signing Section Totals:				\$68,580.00		\$54,818.42		\$55,608.60
Contract Grand Totals:				\$14,053,215.67		\$14,479,476.86		18,177,978.14



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC					
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0005 0110 3 REMOVAL OF EXISTING STRUCTURES/BRIDGES 44925715201/Bridge ID 860018		(5336.000) SF (LS)	150,000.00000	150,000.00				
0010 0110 71 1 BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL		384.000 LF	1,500.00000	576,000.00				
0015 0400143 CLEANING & COATING CONCRETE SURFACE, CLASS 5		55,415.000 SF	6.00000	332,490.00				
0020 0413149 PENETRANT SEALER		7.000 GA	125.00000	875.00				
0025 0413154 CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES		1,800.000 SF	11.00000	19,800.00				
0030 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD		570.000 LF	95.00000	54,150.00				
0035 0460 1 5 STRUCT STEEL - REHABILITATION, BASCULE LEAVES		68,425.000 LB	38.00000	2,600,150.00				
0040 0460 81 RIVETS - HIGH STRENGTH BOLTS, REPLACEMENT		30.000 EA	325.00000	9,750.00				



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC					
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0045 0465 2105 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, F&I SPAN LOCKS		2.000 AS	205,000.00000	410,000.00				
0050 0465 2401 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, RECONDITION, SPEED REDUCER & GEAR TRAIN 44925715201/Bridge ID 860018		(1.000) LS	325,000.00000	325,000.00				
0055 0465 2508 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, ADJUST/MODIFY, LIVE LOAD SHOES 44925715201/Bridge ID 860018		(1.000) LS	44,000.00000	44,000.00				
0060 0465 2605 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, REMOVE & DISPOSE-CONTRACTOR OWNS, SPAN LOCKS		2.000 AS	25,000.00000	50,000.00				
0065 0465 2608 MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, REMOVE & DISPOSE-CONTRACTOR OWNS, LIVE LOAD SHOES 44925715201/Bridge ID 860018		(1.000) LS	40,000.00000	40,000.00				
0070 0465 3 17 MOVABLE BRIDGE COUNTERWEIGHT, F&I, BALANCE BLOCKS		640.000 EA	205.00000	131,200.00				



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC					
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0075 0465 3 50 MOVABLE BRIDGE COUNTERWEIGHT, ADJUST		2.000 EA	15,000.00000	30,000.00				
0080 0465 20 MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR 44925715201/Bridge ID 860018		(397.000) DA (LS)	250,000.00000	250,000.00				
0085 0465 21 MOVABLE BRIDGE OPERATOR		397.000 DA	985.00000	391,045.00				
0090 0465 71 3 MOVABLE BRIDGE FUNCTIONAL CHECKOUT, PHASE C 44925715201/Bridge ID 860018		(1.000) LS	132,500.00000	132,500.00				
0095 0471 3 3 POLYMERIC FENDER SYSTEM, 201-400 KIP-FT 44925715201/Bridge ID 860018		(1.000) LS	3,150,000.00000	3,150,000.00				
0100 0505 2100 ALUMINUM DECK PANELS, FURNISH & INSTALL		5,303.000 SF	445.00000	2,359,835.00				
0105 0508 4 MOVABLE BRIDGE ELECTRICAL EQUIPMENT, REHABILITATION 44925715201/Bridge ID 860018		(1.000) LS	1,350,000.00000	1,350,000.00				
0110 0508 76 1 MOVABLE BRIDGE - REHAB, SPAN MOTORS & CONTROLLERS , F&I 44925715201/Bridge ID 860018		(1.000) LS	500,000.00000	500,000.00				



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC					
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures								
0115 0508 76 4 MOVABLE BRIDGE - REHAB, SPAN MOTORS & CONTROLLERS , REMOVE 44925715201/Bridge ID 860018		(1.000) LS	3,000.00000	3,000.00				
0120 0508 77 1 MOVABLE BRIDGE-REHAB,PROGRAMMABLE LOGIC CONTROLLER F&I		1.000 EA	125,000.00000	125,000.00				
0125 0508 78 1 MOVABLE BRIDGE-REHAB, LIMIT SWITCHES & TRANSDUCERS F&I 44925715201/Bridge ID 860018		(1.000) LS	65,000.00000	65,000.00				
0130 0508 78 4 MOVABLE BRIDGE-REHAB, LIMIT SWITCHES & TRANSDUCERS REMOVE 44925715201/Bridge ID 860018		(1.000) LS	6,500.00000	6,500.00				
0135 0508 79 1 MOVABLE BRIDGE-REHAB,CONTROL CONSOLE, F&I		1.000 EA	525,000.00000	525,000.00				
0140 0508 79 4 MOVABLE BRIDGE-REHAB,CONTROL CONSOLE, REMOVE		1.000 EA	1,850.00000	1,850.00				
0145 0508 80 1 MOVABLE BRIDGE-REHAB, BRAKE SYSTEM, F&I		4.000 EA	95,000.00000	380,000.00				
0150 0508 80 4 MOVABLE BRIDGE-REHAB, BRAKE SYSTEM, REMOVE		4.000 EA	450.00000	1,800.00				



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
			Unit Price	Ext Amount						
SECTION: 0001 Structures										
0155 0508 82 5 MOVABLE BRIDGE-REHAB, CONTROL PANEL - MOTOR CONTROLLER, REPLACE		1.000 EA	95,000.00000	95,000.00						
0160 0508 83202 MOVABLE BRIDGE INTEGRATED DRIVE SYSTEM, REPLACE, 26-40 KW		4.000 EA	95,000.00000	380,000.00						
0165 0512 1 1 MOVABLE BRIDGE-CONTROL HOUSE, RENOVATE 44925715201/Bridge ID 860018		(1.000) LS	685,000.00000	685,000.00						
0170 0561 1 COATING EXISTING STRUCTURAL STEEL 44925715201/Bridge ID 860018		(374.000) TN (LS)	1,850,000.00000	1,850,000.00						
0001 Structures Section Totals:				\$17,024,945.00						

SECTION: 0002 Roadway										
0175 0101 1 MOBILIZATION 44925715201		(1.000) LS	2,000,000.00000	2,000,000.00						
0180 0102 1 MAINTENANCE OF TRAFFIC 44925715201		(397.000) DA (LS)	650,000.00000	650,000.00						
0185 0102 14 TRAFFIC CONTROL OFFICER		4,300.000 HR	85.00000	365,500.00						



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC					
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway								
0190 0102 60 WORK ZONE SIGN		58,003.000 ED	0.25000	14,500.75				
0195 0102 71 13 TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE		372.000 LF	65.00000	24,180.00				
0200 0102 71 23 TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE		372.000 LF	30.00000	11,160.00				
0205 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD		33,675.000 ED	0.20000	6,735.00				
0210 0102 74 8 CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)		9,720.000 FD	0.15000	1,458.00				
0215 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL		579.000 ED	7.00000	4,053.00				
0220 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY		2,574.000 ED	14.00000	36,036.00				
0225 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION		1,588.000 ED	45.00000	71,460.00				



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC					
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway								
0230 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION		1,588.000 ED	45.00000	71,460.00				
0235 0102115 TYPE III BARRICADE		7,595.000 ED	0.45000	3,417.75				
0240 0102913 21 REMOVABLE TAPE, WHITE, SOLID 6"		0.095 GM	22,500.00000	2,137.50				
0245 0102913 31 REMOVABLE TAPE, YELLOW, SOLID, 6"		0.530 GM	22,500.00000	11,925.00				
0250 0104 11 FLOATING TURBIDITY BARRIER		1,000.000 LF	12.00000	12,000.00				
0255 0107 1 LITTER REMOVAL		22.830 AC	250.00000	5,707.50				
0260 0107 2 MOWING		0.940 AC	10,000.00000	9,400.00				
0265 0108 1 MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING 44925715201		(1.000) LS	25,000.00000	25,000.00				



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC						
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount	
SECTION: 0002 Roadway									
0270 0327 70 12 MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH		691.000 SY	35.00000	24,185.00					
0275 0337 7 82 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22		47.500 TN	650.00000	30,875.00					
0280 0520 1 10 CONCRETE CURB & GUTTER, TYPE F		6.000 LF	285.00000	1,710.00					
0285 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK		3.000 SY	285.00000	855.00					
0290 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE		26.000 LF	450.00000	11,700.00					
0295 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE		1.000 EA	6,800.00000	6,800.00					
0300 0695 1 1 TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL		4.000 EA	6,500.00000	26,000.00					
0305 0695 6 11 TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 1 LOOP		8.000 EA	4,500.00000	36,000.00					



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC					
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway								
0310 0706 1 3 RAISED PAVEMENT MARKER, TYPE B		207.000 EA	7.00000	1,449.00				
0315 0710 11101 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"		0.019 GM	3,000.00000	57.00				
0320 0710 11201 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"		0.040 GM	3,000.00000	120.00				
0325 0999 16 PARTNERING, DO NOT BID 44925715201		(1.000) LS	6,000.00000	6,000.00				
0330 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 44925715201		(1.000) LS	129,909.59000	129,909.59				
0002 Roadway Section Totals:				\$3,601,791.09				

SECTION: 0003 Signing								
0335 0700 1111 SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF		1.000 EA	3,000.00000	3,000.00				
0340 0700 1600 SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE		1.000 EA	3,000.00000	3,000.00				



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description () indicates item is bid as Lump Sum	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC					
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing								
0345 0706 1 3 RAISED PAVEMENT MARKER, TYPE B		57.000 EA	7.00000	399.00				
0350 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 44925715201		(1.000) LS	6,500.00000	6,500.00				
0355 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS		17.000 LF	9.00000	153.00				
0360 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAGE		1.000 EA	650.00000	650.00				
0365 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"		0.024 GM	15,500.00000	372.00				
0370 0711 16131 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP		0.034 GM	4,500.00000	153.00				
0375 0711 16201 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"		0.034 GM	16,500.00000	561.00				
0380 0713103101 PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES		0.422 GM	48,500.00000	20,467.00				



Tabulation of Bids

Letting: 04250404 April 04, 2025

Call Order: 001

Contract: E4X35

Line No / Item ID Item Description <i>() indicates item is bid as Lump Sum</i>	Alternate	Quantity Units	(4) SOUTHERN ROAD & BRIDGE, LLC					
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing								
0385 0713103181 PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES		0.415 GM	15,000.00000	6,225.00				
0390 0713103201 PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES		0.422 GM	55,000.00000	23,210.00				
0395 0713103381 PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES		0.415 GM	15,000.00000	6,225.00				
0003 Signing Section Totals:				\$70,915.00				
Contract Grand Totals:				\$20,697,651.09				



Tabulation of Bids

Letting: 04250404 April 04, 2025 **Call Order:** 001 **Contract:** E4X35

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.