

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04181207 Call Order: 006 Proposal: E4T45 District:04
Counties: BROWARD
Road Name: BRIDGE - PAINTING
Limits: 86060007
Project(s): 44145415201(*) Federal Aid No: N/A
Total Roadway Length: 0.170 Miles Contract Days: 264
Total Bridge Length: 0.165 Miles Letting Date: 12/07/18
Total Proposal Length: 0.335 Miles Contract Execution Days:
Special Start Date: N/A
Aquis/Flexible Start Time: 30
Proposal Budget Estimate: \$1,565,385.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of the full removal and replacement of the existing coating system on the exterior structural steel, spot painting of interior structural steel, and application of Class-V Finish to concrete surfaces of Bridge No. 860337 and 860338 in Broward County.

PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PRE-QUALIFIED: Contractor must be pre-qualified.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 006 Proposal: E4T45

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	40,444.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44145415201 860337)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44145415201 860338)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44145415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44145415201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (44145415201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (44145415201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (44145415201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (44145415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	7,690.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	360.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,390.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,080.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	3,070.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	63,852.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	677.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	14.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	866.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	728.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	728.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	4,200.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	4,200.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44145415201)	LS	1.000