

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04190802 Call Order: 001 Proposal: E4T77 District:04

Counties: BROWARD

Road Name: BROWARD COUNTY PUSH BUTTON CONTRACT TRAFFIC SIGNAL CONST

Limits: Midpoint

Project(s): 43633915201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	730
Total Bridge Length:	0.000 Miles	Letting Date:	08/02/19
Total Proposal Length:	0.000 Miles	Contract Execution Days:	
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15

Proposal Budget Estimate: \$1,000,000.00

Please read the full advertisement

Description: Job Order Contracting

The Improvements under this Contract consist of Traffic Control Devices/Systems through a Task Work Document-driven Push-Button contract, at various locations in Broward County.

WORK DRIVEN CONTRACT: The award amount shall be based on the budgeted amount of \$1,000,000.00 and not the contractors bid total over the two (2) year term of the contract.

- The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

- **METHOD OF PROCUREMENT:** This project will be procured using a Bid Factor method.

- o The Department provides quantities and predetermined Base Unit Prices for pay items which are included in the Contract Plans and Advertisement.

- o The Bidder shall propose a single Bid Factor expressed as a number carried out to 3 decimal places. The proposed Bid Factor will be applied to all predetermined pay item Base Unit Prices included in the advertisement.

- o The Bid Factor of 1.000 shall be 100% of the Base Unit Price, any number above 1.000 will increase the Base Unit Price, and any number below 1.000 will decrease the Base Unit Price.

- o The lowest Bidder will be determined by the lowest Bid Factor submitted in response to the advertisement.

- o Award of the contract is based upon the bidder who submits a responsive and responsible bid with the lowest Bid Factor.

- Pre-Qualified: Contractor must be pre-qualified.

- **REQUIRED SUBMITTAL WITH BID:** Bid Factor Bidding Sheet must be submitted with the bid.

- **PERFORMANCE BOND:** A Contract / Performance bond is required for this project

- Award of this contract is contingent upon Annual Legislative Budget Approval of Fiscal Year2020 funds.

Call Order: 001 Proposal: E4T77

ALT	Item	Description	Unit	Quantity
Section 0001 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	15.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	5.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	4.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	15.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	15.000

Call Order: 001 Proposal: E4T77

ALT	Item	Description	Unit	Quantity
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	15.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	10.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	5.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	5.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	2.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	2.000
	0700- 12- 22	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, TWO BEACONS	AS	2.000
	0700- 12- 31	SIGN BEACON, F&I OVERHEAD MOUNT, ONE BEACON	AS	2.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	60.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	300.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	500.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	20.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	150.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	5.000
Section 0002 Signalization				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	64.000
	0102- 60-	WORK ZONE SIGN	ED	3,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,000.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	100.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	500.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	300.000
	0104- 10- 3	SEDIMENT BARRIER	LF	150.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	0.100
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	30.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	50.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	100.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	50.000
	0527- 2-	DETECTABLE WARNINGS	SF	100.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	900.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	450.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	1,000.000

Call Order: 001 Proposal: E4T77

ALT	Item	Description	Unit	Quantity
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	500.000
	0634- 4-151	SPAN WIRE ASSEMBLY, F&I, TWO POINT, PERPENDICULAR	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	35.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	10.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	4.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	2,000.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	4.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0641- 2- 14	PRESTRESSED CONCRETE POLE, F&I, TYPE P-IV	EA	2.000
	0641- 2- 16	PRESTRESSED CONCRETE POLE, F&I, TYPE P-VI	EA	2.000
	0641- 2- 17	PRESTRESSED CONCRETE POLE, F&I, TYPE P-VII	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	8.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	8.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	2.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	2.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	2.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	2.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	40.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	5.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	8.000
	0650- 1- 24	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W/ALUM TOP, 3 SECTION, 1 WAY	AS	2.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	10.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	4.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	8.000
	0654- 2- 22	RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL-SOLAR POWERED, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	2.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	8.000
	0660- 4- 42	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE ABOVE GROUND EQUIPMENT	EA	8.000

Call Order: 001 Proposal: E4T77

ALT	Item	Description	Unit	Quantity
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	32.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	8.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	4.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	4.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	4.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	4.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	500.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	500.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	2.000