

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04190104 Call Order: 001 Proposal: E4S19 District:04
Counties: PALM BEACH
Road Name: SR-800/SPANISH RIVER BLVD
Limits: 93002000
Project(s): 43215415201(*) Federal Aid No: N/A
Total Roadway Length: 0.092 Miles Contract Days: 150
Total Bridge Length: 0.184 Miles Letting Date: 01/04/19
Total Proposal Length: 0.276 Miles Contract Execution Days:
Special Start Date: N/A
Aquis/Flexible Start Time: 45
Proposal Budget Estimate: \$3,121,549.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of full removal and replacement of the existing structural steel coating system, rehabilitation and recondition of span locks, and removal and installation of pile jackets on Spanish River Boulevard over Intracoastal Waterway's Bridge Nos. 930154 and 930226 in Palm Beach County.

PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PRE-QUALIFIED: Contractor must be pre-qualified.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 001 Proposal: E4S19

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43215415201 930154)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43215415201 930226)	LS	1.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	326.000
	0457- 2-231	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, GREATER THAN 30.", GALVANIC SYSTEM	LF	326.000
	0465- 2-405	MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, RECONDITION,SPAN LOCKS	AS	4.000
	0465- 2-508	MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, ADJUST/MODIFY, LIVE LOAD SHOES (43215415201 930154)	LS	1.000
	0465- 2-508	MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, ADJUST/MODIFY, LIVE LOAD SHOES (43215415201 930226)	LS	1.000
	0465- 2-605	MOVABLE BRIDGE MACHINERY & CASTING-REHABILITATION, REMOVE & DISPOSE-CONTRACTOR OWNS, SPAN LOCKS	AS	4.000
	0465- 3- 50	MOVABLE BRIDGE COUNTERWEIGHT, ADJUST	EA	2.000
	0465- 3- 50	MOVABLE BRIDGE COUNTERWEIGHT, ADJUST (43215415201)	EA	2.000
	0465- 20-	MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR (43215415201 930154)	LS	1.000
	0465- 20-	MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR (43215415201 930226)	LS	1.000
	0465- 21-	MOVABLE BRIDGE OPERATOR	DA	150.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43215415201 930154)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43215415201 930226)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43215415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43215415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,057.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,815.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	555.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	80.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	181.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	569.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	353.000
	0999- 16-	PARTNERING, DO NOT BID (43215415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43215415201)	LS	1.000