

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 04190308 Call Order: 005 Proposal: E4T52 District:04

Counties: BROWARD

Road Name: SR A1A/DANIA BEACH BLVD FROM OCEAN DRIVE TO GULFSTREAM ROAD

Limits: 86030000

Project(s): 43784715201(*) Federal Aid No: N/A

| | | | |
|------------------------|-------------|----------------------------|----------|
| Total Roadway Length: | 2.542 Miles | Contract Days: | 182 |
| Total Bridge Length: | 0.000 Miles | Letting Date: | 03/08/19 |
| Total Proposal Length: | 2.542 Miles | Contract Execution Days: | |
| | | Special Start Date: | N/A |
| | | Aquis/Flexible Start Time: | 15 |

Proposal Budget Estimate: \$1,445,276.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, milling and resurfacing with overbuild, minor widening, concrete sidewalk and driveways, signing and pavement markings, selective clearing and grubbing, and monitoring exiting structures along State Road A1A (Dania Beach Boulevard) from Gulfstream Road easterly 1.271 miles in the Cities of Dania Beach and Hollywood, Broward County.

Call Order: 005 Proposal: E4T52

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|-------------|---|------|------------|
| Section 0001 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (43784715201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (43784715201) | LS | 1.000 |
| | 0102- 2- 1 | SPECIAL DETOUR 1 (43784715201) | LS | 1.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 2,887.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 29,997.000 |
| | 0102- 74- 7 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | LF | 4,746.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 249.000 |
| | 0102- 78- | TEMPORARY RETROREFLECTIVE PAVEMENT MARKER | EA | 192.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 392.000 |
| | 0104- 10- 3 | SEDIMENT BARRIER | LF | 15,048.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 9.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 72.740 |
| | 0107- 2- | MOWING | AC | 52.520 |
| | 0108- 1- | MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43784715201) | LS | 1.000 |
| | 0110- 1- 1 | CLEARING & GRUBBING (43784715201) | LS | 1.000 |
| | 0110- 2- 2 | SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN | AC | 0.430 |
| | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE | SY | 2,523.000 |
| | 0120- 1- | REGULAR EXCAVATION | CY | 1,732.000 |
| | 0120- 6- | EMBANKMENT | CY | 25.000 |
| | 0160- 4- | TYPE B STABILIZATION | SY | 1,667.000 |
| | 0285-709- | OPTIONAL BASE, BASE GROUP 09 | SY | 1,504.000 |
| | 0285-714- | OPTIONAL BASE, BASE GROUP 14 | SY | 1,320.000 |

Call Order: 005 Proposal: E4T52

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|---|------|------------|
| | 0327- 70- 6 | MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH | SY | 30,067.000 |
| | 0334- 1- 13 | SUPERPAVE ASPHALTIC CONC, TRAFFIC C | TN | 234.600 |
| | 0337- 7- 83 | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22 | TN | 2,710.000 |
| | 0520- 1- 10 | CONCRETE CURB & GUTTER, TYPE F | LF | 3,171.000 |
| | 0520- 5- 41 | TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE | LF | 1,343.000 |
| | 0522- 1- | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK | SY | 2,516.000 |
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 238.000 |
| | 0523- 1- 3 | PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE | SY | 75.000 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 3,738.000 |
| | 0695- 7-600 | TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET | EA | 1.000 |
| | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6" | GM | 1.130 |
| | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8" | GM | 0.026 |
| | 0710- 11-131 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE | GM | 0.946 |
| | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM | 0.090 |
| | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS | EA | 11.000 |
| | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6" | GM | 0.818 |
| | 0710- 11-241 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6" | GM | 0.031 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43784715201) | LS | 1.000 |
| Section 0002 Signing | | | | |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 29.000 |
| | 0700- 1- 12 | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF | AS | 2.000 |
| | 0700- 1- 50 | SINGLE POST SIGN, RELOCATE | AS | 1.000 |
| | 0700- 1- 60 | SINGLE POST SIGN, REMOVE | AS | 23.000 |
| | 0700- 2- 13 | MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF | AS | 1.000 |
| | 0700- 2- 14 | MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF | AS | 1.000 |
| | 0700- 2- 60 | MULTI- POST SIGN, REMOVE | AS | 2.000 |
| | 0710- 90- | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43784715201) | LS | 1.000 |
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 172.000 |
| | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS | LF | 233.000 |
| | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK | LF | 32.000 |
| | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" | GM | 0.351 |
| | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW | EA | 16.000 |
| | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6" | GM | 0.091 |
| | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE | EA | 38.000 |
| | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW | EA | 22.000 |
| | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" | GM | 2.799 |
| | 0711- 16-102 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8" | GM | 0.031 |

Call Order: 005 Proposal: E4T52

| ALT | Item | Description | Unit | Quantity |
|-----|--------------|--|------|----------|
| | 0711- 16-131 | THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP | GM | 1.881 |
| | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" | GM | 1.704 |