

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 04190308 Call Order: 002 Proposal: E4T56 District:04

Counties: BROWARD

Road Name: SR/7 US-441 FROM NW 29TH STREET TO NORTH OF SR816

Limits: 86100000

Project(s): 43578125201(*) Federal Aid No: N/A

Total Roadway Length:	0.720 Miles	Contract Days:	203
Total Bridge Length:	0.000 Miles	Letting Date:	03/08/19
Total Proposal Length:	0.720 Miles	Contract Execution Days:	
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: \$1,265,816.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, widening, concrete sidewalk and driveway, detectable warnings, concrete curb and gutter, architectural concrete pavers, concrete removal, selective clearing and grubbing, pedestrian channelizing barrier, pipe handrail, drainage, signing and pavement markings, signalization, landscape and irrigation system repairs along State Road 7 (US-441) from N.W. 29th Street to 520 feet north of State Road 816 (Oakland Park Boulevard) in the City of Lauderdale Lakes, Broward County.

Pre-Qualified: Contractor must be pre-qualified

PERFORMANCE BOND: A Contract / Performance bond is required for this project

Call Order: 002 Proposal: E4T56

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43578125201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43578125201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	24.000
	0102- 60-	WORK ZONE SIGN	ED	6,520.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	13,398.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	406.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	233.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	406.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	434.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	406.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	406.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	14.000
	0107- 1-	LITTER REMOVAL	AC	16.480
	0107- 2-	MOWING	AC	9.380
	0110- 1- 1	CLEARING & GRUBBING (43578125201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.020
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,062.000
	0120- 1-	REGULAR EXCAVATION	CY	335.000

Call Order: 002 Proposal: E4T56

ALT	Item	Description	Unit	Quantity
	0120- 6-	EMBANKMENT	CY	584.000
	0160- 4-	TYPE B STABILIZATION	SY	1,347.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	113.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	23,741.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	12.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,967.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.100
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	9.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	5.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	38.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	41.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,394.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	15.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,286.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	156.000
	0527- 2-	DETECTABLE WARNINGS	SF	204.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,495.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.379
	0914-550- 15	FENCING- PEDESTRIAN BARRIER, P1 STEEL LOOP, PROJECT 435781-2-52-01	LF	783.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43578125201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	18.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	19.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43578125201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.043
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	73.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	459.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.290
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	43.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	155.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.050

Call Order: 002 Proposal: E4T56

ALT	Item	Description	Unit	Quantity
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	2,245.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,977.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.422
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.124
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.720
Section 0003 Lighting				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	40.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	80.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	3.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	9.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	3.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	3.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
Section 0005 Landscape / Peripheral				
	0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS (43578125201)	LS	1.000
	0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (43578125201)	LS	1.000
	0580- 2- 4	LANDSCAPE- RELOCATE TREE, TREES <5" CALIPER	EA	5.000
	0580- 2- 5	LANDSCAPE- RELOCATE TREE, TREES >5" CALIPER	EA	8.000
	0580- 2- 7	LANDSCAPE- RELOCATE TREE, PALMS <14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	12.000
	0580- 2- 8	LANDSCAPE- RELOCATE TREE, PALMS >14' OF CLEAR TRUNK SABAL PALM ONLY	EA	13.000
	0590- 70- 1	IRRIGATION SYSTEM REPAIRS (43578125201)	LS	1.000