

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 04190503      Call Order: 002      Proposal: E4T66-R0      District:04  
Counties: DIST/ST-WIDE  
Road Name: D/W STRUCTURE REPAIRS PUSHBUTTON - ROUTINE MAINTENANCE  
Limits: Midpoint  
Project(s): 44476817201(\*)      Federal Aid No: N/A  
Total Roadway Length: 0.000 Miles      Contract Days: 730  
Total Bridge Length: 0.000 Miles      Letting Date: 05/03/19  
Total Proposal Length: 0.000 Miles      Contract Execution Days: 10  
Special Start Date: 04/03/19  
Aquis/Flexible Start Time: 13  
Proposal Budget Estimate: \$200,000.00

Please read the full advertisement

**Description:**

The work under this Contract consists of providing all labor, materials, equipment and incidentals necessary to perform routine and priority repairs on bridges and miscellaneous structures including, but not limited to, integral pile jackets, cathodic protection, the repair or replacement of expansion joints, concrete headers, concrete parapets, fender systems, structural steel – welding, beam strand and bar splices, crack injection and sealing, concrete spalls, rip rap, cleaning concrete surfaces, flowable fill, aluminum handrail, concrete slope pavement and other miscellaneous concrete repairs, at various locations throughout District 4.

**MAXIMUM LIMITING:** The contract bond and award will be based on the maximum limiting budget amount of \$200,0000 and not the contractors bid. There is no guarantee of minimum or maximum amount to be issued under this contract.

**REQUIRED SUBMITTAL WITH BID:** Experience in Bridge Repair. Work Experience Form 850-070-04 must be submitted with the bid.

**PERFORMANCE BOND:** A Contract / Performance bond is required for this project.

**Call Order: 002 Proposal: E4T66-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 CONCRETE REPAIR (CY)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	100.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	200.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES	LS	1.000
	0110- 71- 1	BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL	LF	15.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	20.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT:	LF	600.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	3.000
	0400- 2- 5	CONCRETE CLASS II, BRIDGE SUBSTRUCTURE	CY	3.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	3.000
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	3.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	3.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	2,000.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	2,000.000
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	12.000
	0401- 70- 1	RESTORE SPALLED AREAS, EPOXY	CF	10.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	10.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	10.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	50.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	280.000
	0450- 83- 1	BEAM REPAIR, STRAND SPLICES	EA	1.000
	0450- 83- 2	BEAM REPAIR, BAR SPLICES	EA	1.000
	0457- 1- 22	STANDARD INTEGRAL PILE JACKET, STRUCTURAL, 16.1 to 30.0"	LF	10.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	10.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	200.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	10.000
	0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES	LB	50.000
	0460- 94-	STRUCTURAL STEEL REPAIR- WELDS	LF	25.000
	0471- 1- 1	FENDER SYSTEM,PLASTIC MARINE LUMBER,REINFORCED	MB	0.200
	0471- 1- 2	FENDER SYSTEM,PLASTIC MARINE LUMBER, NON-REINFORCED	MB	0.500
	0524- 2- 2	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 4"	SY	20.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	20.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	35.000
	0649- 26- 1	STEEL MAST ARM ASSEMBLY, REMOVE, POLE ONLY- ENTIRE FOUNDATION REMAINS	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	2.000
	0649- 26- 7	STEEL MAST ARM ASSEMBLY, REMOVE, REMOVE ARM AND ATTACHMENTS; POLE REMAINS	EA	1.000
	0700- 4-610	OVERHEAD STATIC SIGN STRUCTURE, REMOVE CANTILEVER	EA	2.000
	0700- 4-620	OVERHEAD STATIC SIGN STRUCTURE, REMOVE SPAN	EA	1.000
	0715- 19- 60	HIGH MAST LIGHT POLE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715- 19- 61	HIGH MAST LIGHT POLE, REMOVE POLE- FOUNDATION REMAINS	EA	1.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	1.000