

## Addendum No. 9 Memorandum

DATE: March 17, 2017  
 TO: District Contracts / Final Plans  
 FROM: Vanita Saini, Project Manager  
 COPIES: File  
 SUBJECT: Addendum Number 9 - Letting (mo./yr.) 4/2017  
 Financial Project ID 433108-6-52-01 (Lead number only)  
 Proposal/Contract ID E4R96  
 Federal Funds:  No  Yes Federal Aid No. 0951-691-1  
 County: Broward State Road No. 9

Concurred by: Robert Bostian Date: 3/17/2017  
 Signature of Alternate Contracting Coordinator (John Olson (primary) / Robert Bostian (alternate)) or Designee.

Legal Approval Date: DR 3/17/2017  
 (Dawn Raduano)

Central Office Approval Date: 3/20/17  
 (State Construction Office – Larry Ritchie)

FHWA Concurrence Date: 3-20-17  
 (FHWA Florida Division Office – Mark Clasgens)

CONTRACT TIME REVISED:  No  Yes (If yes, \_\_\_\_\_ Calendar Days)

<u>Page No(s).</u>	<u>Rev. Date</u>	<u>Description</u>
RFP, pg. iv	3/17/17	Updated the Attachments listing as follows: A. Project Advertisement B. Division I Design-Build Specifications <del>(DRAFT)</del>
RFP, pg. vi	3/17/17	Updated the Reference Documents listing as follows: <u>4. Miscellaneous</u> Florida's Turnpike Enterprise Shop Drawing Review Process For Design-Build Projects <u>Highway Maintenance Memorandum of Agreements (DRAFT)</u> Incident Management Plan
RFP, pg. 35	3/17/17	Section V.F – Railroad Coordination, Subsection Construction and Railroad Flagging Services has been revised as follows: "South Florida Regional Transportation Authority <u>899801</u> NW 33 <sup>rd</sup> Street"
RFP, pgs. 58&59	3/17/17	Section V.DD – Routine Maintenance Responsibilities has been revised as follows: "Landscape areas as defined in Article 7-11 Preservation of Property other than areas under MMOA's are located in Palm

Beach County between milepost 0.111 and milepost 0.995 off the right northbound shoulder for a total of 1.5 acres.

The Design-Build Firm shall be responsible for complying with the conditions contained in the MMOA for the Palmetto Park Road Shared Use Path during construction through final acceptance.

RFP, pg. 71      3/17/17      Section VI.F – Geometric Design, Subsection General has been revised as follows:  
 “The Design-Build Firm shall be solely responsible for the development of a design that meets all applicable standards and criteria.

The Design-Build Firm shall construct the complete roadway typical section template (milling, resurfacing, and overbuild, as well as roadside swales and side slopes) complete to the northern project limits at Sta. 3190+00. The appropriate PPM compliant transitions to the existing roadway and roadside elements to remain shall be performed north of Sta. 3190+00, within the Phase 3B-2 Project limits.”

RFP, pg. 85      3/17/17      Section VI.H.4 – Noise Walls has been revised as follows:

Noise Wall Table						
Noise Wall Number	From Station	To Station	Approx. Length	Side	Adjacent Community	Type of Noise Wall
1	2755+10	3021+85	4,305'	Right	Tivoli Park and Natura	22' Tall Ground Mounted
2	3059+00	3067+20	820'	Right	Palm Beach Farms	8' Tall Shoulder Mounted Replacement
3	3078+60	3091+95	1,335'	Left	Mizner Forest	20' Tall Ground Mounted
4	3115+52	~ 3137+63	~2,222'	Right	Boca Raton Square, Raintree, and Palmetto Park West	8' Tall Shoulder Mounted Replacement
5	3136+48	3149+36	1,294'	Right	Palmetto Park West	8' Tall Shoulder Mounted Replacement
6	3173+38	3184+96	1,230'	Left	Fairfield Gardens	22' Tall Ground Mounted
7	3169+50	3173+50	400'	Right	Country Club Village	14' Tall Shoulder Mounted or 8' Tall Retaining Wall Mounted

“For Noise Wall Number 7, the height of the shoulder mounted noise wall shall be 14 feet, unless mounted on retaining walls, in which case the height shall be 8 feet.”

Attachment B      3/17/17      Finalized Division I Design-Build Specifications

Ref Doc. 4      3/17/17      Revised Load Rating Report for I-95 bridges over Camino Real Added Draft Maintenance Memorandum of Agreements