

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04191101 Call Order: 001 Proposal: E4U16 District:04

Counties: PALM BEACH

Road Name: PALM BEACH COUNTY - SIGNING/PAVEMENT MARKINGS

Limits: Midpoint

Project(s): 42925035201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	730
Total Bridge Length:	0.000 Miles	Letting Date:	11/01/19
Total Proposal Length:	0.000 Miles	Contract Execution Days:	
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15

Proposal Budget Estimate: \$600,000.00

Please read the full advertisement

Description: Job Order Contracting

The Improvements under this Contract consist of but not limited to, Roadway Signing and Pavement Markings through a Task Work Order/Work Document driven, Push-Button contract at various locations in Palm Beach County Florida.

WORK DRIVEN CONTRACT: The award amount shall be based on the budgeted amount of \$600,000.00 and not the contractors bid total over the two (2) year term of the contract.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Department's estimated quantities and the Contractor's bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

METHOD OF PROCUREMENT: This project will be procured using a Bid Factor method.

The Department provides quantities and predetermined Base Unit Prices for pay items which are included in the Contract Plans and Advertisement.

The Bidder shall propose a single Bid Factor expressed as a number carried out to 3 decimal places. The proposed Bid Factor will be applied to all predetermined pay item Base Unit Prices included in the advertisement.

The Bid Factor of 1.000 shall be 100% of the Base Unit Price, any number above 1.000 will increase the Base Unit Price, and any number below 1.000 will decrease the Base Unit Price.

The lowest Bidder will be determined by the lowest Bid Factor submitted in response to the advertisement.

Award of the contract is based upon the bidder who submits a responsive and responsible bid with the lowest Bid Factor.

Pre-Qualified: Contractor must be pre-qualified.

REQUIRED SUBMITTAL WITH BID: Bid Factor Bidding Sheet must be submitted with the bid.

PERFORMANCE BOND: A Contract / Performance bond is required for this project

Call Order: 001 Proposal: E4U16

ALT	Item	Description	Unit	Quantity
Section 0001 Signing				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	40.000
	0102- 60-	WORK ZONE SIGN	ED	1,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,000.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	400.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	600.000

Call Order: 001 Proposal: E4U16

ALT	Item	Description	Unit	Quantity
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	240.000
	0523- 1- 3	PATTERNED PAVEMENT, VEHICULAR AREAS- GREEN BIKE LANE	SY	240.000
	0527- 2-	DETECTABLE WARNINGS	SF	140.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	100.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	15.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	20.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	15.000
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	AS	6.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	30.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	50.000
	0700- 2- 11	MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	5.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	5.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	5.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	20.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	15.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	10.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	15.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	10.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	15.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	10.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	5.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	15.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	75.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	35.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	75.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	250.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	300.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.250
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	25.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	100.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.250
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	700.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	500.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	50.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	50.000

Call Order: 001 Proposal: E4U16

ALT	Item	Description	Unit	Quantity
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	10.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.250
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.250
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.250
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.250
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.250
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.250