

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 04200403 Call Order: 004 Proposal: E4U56-R0 District:04
Counties: DIST/ST-WIDE, MARTIN, ST LUCIE
Road Name: TREASURE COAST NPDES CORRECTIVE ACTIONS
Limits: Midpoint
Project(s): 42833557201(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: 365
Total Bridge Length: 0.000 Miles Letting Date: 04/03/20
Total Proposal Length: 0.000 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 13
Proposal Budget Estimate: \$130,000.00

Please read the full advertisement

Description:

The work under this Contract consists of all labor, equipment, materials and incidentals necessary to rehabilitate any part of the drainage system assets, video, remove and dispose of any type of blockage inside of any part of the storm drainage system to provide maximum drainage capacity of the Department s storm water system in Martin, St. Lucie, and Indian River Counties. The summary of pay items for this project is listed in the Bid Price Proposal.

Maximum Limiting: The award amount and contract performance bond shall be based on the maximum limited budget amount of \$130,000.00 and not the contractors bid total. There is no guarantee of minimum or maximum amount to be issued under this contract.

PERFORMANCE BOND: A Contract Performance bond is required for this project.

Award of this contract is contingent upon Annual Legislative Budget Approval of Fiscal Year 2021 fund.

The Notice to Proceed may not be issued until July 1, 2020. The contract may be executed with a reviewed funds approval as long as no work is allowed to begin until July 1, 2020 (as evidenced by the NTP).

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 004 Proposal: E4U56-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	8,200.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	1,001.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	1,503.000
	0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	799.000
	0430- 94- 5	DESILTING PIPE, 61" OR GREATER	LF	250.000
	0430-821- 23	CLEANING & SEALING EXISTING PIPE JOINT, 15" STORM SEWER	EA	10.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	10.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	5.000
	0430-821- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" STORM SEWER	EA	5.000
	0430-821- 38	CLEANING & SEALING EXISTING PIPE JOINT, 36" STORM SEWER	EA	5.000
	0430-821- 40	CLEANING & SEALING EXISTING PIPE JOINT, 42", STORM SEWER	EA	5.000
	0430-821- 41	CLEANING & SEALING EXISTING PIPE JOINT, 48", STORM SEWER	EA	5.000
	0430-821- 42	CLEANING & SEALING EXISTING PIPE JOINT, 54", STORM SEWER	EA	3.000
	0430-821- 43	CLEANING & SEALING EXISTING PIPE JOINT, 60", STORM SEWER	EA	1.000
	0430-821- 61	CLEANING & SEALING EXISTING PIPE JOINT, >60", STORM SEWER	EA	1.000
	0430-822- 15	CLEANING & SEALING EXISTING PIPE JOINT, 15" CD	EA	8.000
	0430-822- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" CD	EA	5.000
	0430-822- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" CD	EA	5.000
	0430-822- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" CD	EA	5.000
	0430-822- 38	CLEANING & SEALING EXISTING PIPE JOINT, 36" CD	EA	8.000
	0430-822- 42	CLEANING & SEALING EXISTING PIPE JOINT, 54" CD	EA	1.000
	0430-822- 43	CLEANING & SEALING EXISTING PIPE JOINT, 60" CD	EA	1.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	25.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	4.000
	0444- 72- 11	DEEP WELL CLEANING, 24"	LF	150.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	10.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	16.000
	E430-949- 13	DESILTING PIPE (UNDERDRAIN) (4")	LF	55.000
	E430-949- 16	DESILTING PIPE (UNDERDRAIN) (6")	LF	100.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	25.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	20.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	20.000
	E431- 1- 24	PIPE LINER, CURED IN PLACE, 49-60"	LF	10.000
	E431- 1- 25	PIPE LINER, CURED IN PLACE, 61" AND GREATER	LF	5.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	12,501.000