

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04201218 Call Order: 002 Proposal: E4U81-R0 District:04

Counties: DIST/ST-WIDE

Road Name: D/W DRAINAGE PUSH BUTTON MAINTENANCE - DRAINAGE IMPROVEMENTS

Limits: Midpoint

Project(s): 42952847201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	12/18/20
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	13

Proposal Budget Estimate: \$800,000.00

Please read the full advertisement

Description:

The work under this Contract consists of providing all labor, materials, equipment, and incidentals necessary to perform drainage repairs, installation, and maintenance on State roadways within District 4

MAXIMUM LIMITING: The award amount and the contract performance bond shall be based on the maximum limiting budget amount of \$800,000.00 and not the contractor's bid total.

REQUIRED SUBMITTAL WITH BID: Experience in Drainage Repair. Work experience form must be submitted with the bid.

PERFORMANCE BOND: A Contract / Performance bond is required for this project

Call Order: 002 Proposal: E4U81-R0

ALT	Item	Description	Unit	Quantity
Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF)				
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	50.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	75.000
	0102- 60-	WORK ZONE SIGN	ED	800.000
	0102- 61-	BUSINESS SIGN	EA	15.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	60.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	60.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	10.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	10.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	15.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	30.000
	0104- 10- 3	SEDIMENT BARRIER	LF	150.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	40.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	150.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	2.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	200.000
	0120- 1-	REGULAR EXCAVATION	CY	200.000

Call Order: 002 Proposal: E4U81-R0

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	100.000
	0120- 4-	SUBSOIL EXCAVATION	CY	100.000
	0120- 5-	CHANNEL EXCAVATION	CY	100.000
	0120- 6-	EMBANKMENT	CY	200.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	50.000
	0125- 3-	SELECT BEDDING MATERIAL	CY	30.000
	0160- 4-	TYPE B STABILIZATION	SY	200.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	200.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	200.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	50.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	500.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	50.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	25.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	25.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	100.000
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	55.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	55.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	55.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	20.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	6.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	6.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	6.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	6.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	6.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	6.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	6.000
	0425- 1-523	INLETS, DT BOT, TYPE C,JBOT, <10'	EA	6.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	6.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	6.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	6.000
	0425- 1-713	INLETS, GUTTER, TYPE V, J BOT, <10'	EA	6.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	2.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	2.000
	0425- 2-110	MANHOLES, REPAIR	EA	2.000
	0425- 3- 41	JUNCTION BOX, DRAINAGE, P-7, <10'	EA	2.000
	0425- 3- 42	JUNCTION BOXES, P-7, >10'	EA	2.000
	0425- 3- 43	JUNCTION BOX, DRAINAGE, P-7, PARTIAL	EA	2.000
	0425- 3- 61	JUNCTION BOXES, J-7, <10'	EA	2.000
	0425- 3- 63	JUNCTION BOXES, DRAINAGE, J-7, PARTIAL	EA	2.000
	0425- 4-	INLETS, ADJUST	EA	8.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000

Call Order: 002 Proposal: E4U81-R0

ALT	Item	Description	Unit	Quantity
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	15.000
	0425- 10-	YARD DRAIN	EA	1.000
	0430- 95- 1	OUTFALL BARNACLE REMOVAL, 0 - 24"	LF	10.000
	0430- 95- 2	OUTFALL BARNACLE REMOVAL, 25 - 36"	LF	10.000
	0430- 95- 3	OUTFALL BARNACLE REMOVAL, 37-48"	LF	10.000
	0430- 95- 4	OUTFALL BARNACLE REMOVAL, 49-60"	LF	10.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	60.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	60.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	15.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	15.000
	0430-174-248	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 48"SD	LF	15.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	15.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	15.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	15.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	15.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	15.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	15.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	15.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	15.000
	0430-200- 25	FLARED END SECTION, CONCRETE, 18"	EA	4.000
	0430-200- 29	FLARED END SECTION, CONCRETE, 24"	EA	4.000
	0430-200- 33	FLARED END SECTION, CONCRETE, 30"	EA	4.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-524-200	STRAIGHT CONCRETE ENDWALLS, 24", DOUBLE, 0 DEGREES, ROUND	EA	1.000
	0430-963- 1	PVC PIPE FOR BACK OF SIDEWALK, 4"	LF	35.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	2.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0430-982-641	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 48" CD	EA	2.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	15.000
	0440- 1- 10	UNDERDRAIN, TYPE I	LF	10.000
	0440- 1- 20	UNDERDRAIN, TYPE II	LF	10.000
	0440- 70-	UNDERDRAIN INSPECTION BOX	EA	1.000
	0440- 73- 1	UNDERDRAIN OUTLET PIPE, 4"	LF	10.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	10.000
	0440- 73- 3	UNDERDRAIN OUTLET PIPE, 8"	LF	10.000
	0440- 73- 4	UNDERDRAIN OUTLET PIPE, 10"	LF	10.000
	0443- 70- 3	FRENCH DRAIN, 18"	LF	15.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	100.000

Call Order: 002 Proposal: E4U81-R0

ALT	Item	Description	Unit	Quantity
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	30.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	30.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	15.000
	0515- 1- 42	PIPE HANDRAIL - GUIDERAIL, RELOCATE, ALUMINUM	LF	15.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	300.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	20.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	20.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	15.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	60.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	60.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	15.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	15.000
	0527- 2-	DETECTABLE WARNINGS	SF	20.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	10.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	8.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	8.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	35.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	5.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	15.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	7.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.000
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	60.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	60.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	60.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	10.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.000
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.000
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	60.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	1.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	110.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	110.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	110.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	110.000

Call Order: 002 Proposal: E4U81-R0

ALT	Item	Description	Unit	Quantity
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	110.000
	E431- 1- 11	PIPE LINER, SPRAY APPLICATION,0-24"	LF	5.000
	E431- 1- 12	PIPE LINER, SPRAY APPLICATION,25-36"	LF	5.000
	E431- 1- 13	PIPE LINER, SPRAY APPLICATION,37-48"	LF	5.000
	E431- 1- 14	PIPE LINER, SPRAY APPLICATION,49-60"	LF	5.000
	E431- 1- 15	PIPE LINER, SPRAY APPLICATION,61" AND GREATER	LF	5.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	5.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	5.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	5.000
	E431- 1- 24	PIPE LINER, CURED IN PLACE, 49-60"	LF	5.000
	E431- 1- 25	PIPE LINER, CURED IN PLACE, 61" AND GREATER	LF	5.000
	E431- 1- 31	PIPE LINER, SLIP LINER, 0-24"	LF	5.000
	E431- 1- 32	PIPE LINER, SLIP LINER, 25-36"	LF	5.000
	E431- 1- 33	PIPE LINER, SLIP LINER, 37-48"	LF	5.000
	E431- 1- 34	PIPE LINER, SLIP LINER, 49-60"	LF	5.000
	E431- 1- 35	PIPE LINER, SLIP LINER, 61" AND GREATER	LF	5.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	100.000
	E575- 1-	SODDING	SY	80.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	35.000