

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04200207 Call Order: 003 Proposal: E4T86 District:04
Counties: BROWARD, DIST/ST-WIDE, INDIAN RIVER, MARTIN, PALM BEACH, ST LUCIE
Road Name: SOUTH FL RAIL CORRIDOR DYNAMIC ENVELOPE PAVEMENT MARKING
Limits: 86014000
Project(s): 44061215201(*) Federal Aid No: N/A
Total Roadway Length: 1.010 Miles Contract Days: 66
Total Bridge Length: 0.000 Miles Letting Date: 02/07/20
Total Proposal Length: 1.010 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 45 Calendar Days
Proposal Budget Estimate: \$611,335.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of but not limited to, milling and resurfacing (three of twelve locations), signing (solar-powered, single-post, panel), and pavement markings (RPM, delineator posts, painted, thermoplastic, preformed thermoplastic) at 12 railroad crossings along the South Florida Rail Corridor (Hallandale Beach Blvd, Pembroke Rd, Griffin Rd, Oakland Park Blvd, Powerline Rd, Commercial Blvd, Hillsboro Blvd, Yamato Rd, Linton Blvd, Forest Hill Blvd, Summit Blvd, and Okeechobee Blvd) throughout District 4.

Insurance: Contractor must provide the following Insurance cover:

- 1) Insurance Required for Construction at Railroads: Procure and maintain Railroad Protective Liability Coverage (ISO Form CG 00 35) where the railroad is the Named Insured and where the limits are not less than \$2,000,000 combined single limit for bodily injury and/or property damage per occurrence, and with an annual aggregate limit of not less than \$6,000,000. The railroad shall also be added along with the Department as an Additional Insured on the policy/ies procured pursuant to subsection 7-13.2. The insurance described herein shall be maintained through final acceptance of the work. Both the Department and the railroad shall be notified in writing within ten days of any cancellation, notice of cancellation, renewal, or proposed change to any policy or coverage described herein. The Department's approval or failure to disapprove any policy/ies, coverage, or ACORD Certificates shall not relieve or excuse any obligation to procure and maintain the insurance required herein, nor serve as a waiver of any rights the Department may have.
- 2) Insurance for Protection of Utility Owners
- 3) Workers' Compensation Insurance
- 4) Commercial General Liability Insurance

Pre-Qualified: Contractor must be pre-qualified.

Performance Bond: A Contract / Performance bond is required for this project.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 003 Proposal: E4T86

ALT	Item	Description	Unit	Quantity
Section 0001 Signing				
	0101- 1-	MOBILIZATION (44061215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44061215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	389.000
	0102- 60-	WORK ZONE SIGN	ED	2,134.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,906.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	50.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	264.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	468.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	809.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	44.400
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	30.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	8.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	12.000
	0700- 6- 21	HIGHLIGHTED SIGN, F&I GROUND MOUNT- SOLAR POWERED, UP TO 12 SF	AS	47.000
	0700- 6- 22	HIGHLIGHTED SIGN, F&I GROUND MOUNT- SOLAR POWERED, 12-20 SF	AS	2.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	592.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	327.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	65.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	231.000
	0711- 14-002	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 4" FOR RAIL DYNAMIC ENVELOPE, PROJECT 440612-1-52-01	LF	3,690.000
	0711- 14-003	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 16" FOR RAIL DYNAMIC ENVELOPE, PROJECT 440612-1-52-01	LF	6,548.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	12.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.196
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.003
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.148
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44061215201)	LS	1.000