

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 04200103 Call Order: 003 Proposal: E4T89 District:04

Counties: BROWARD

Road Name: SR-84 BRIDGE #860008 OVER THE SOUTH FORK OF THE NEW RIVER

Limits: 86080000

Project(s): 43214615201(*) Federal Aid No: N/A

Total Roadway Length:	0.044 Miles	Contract Days:	89
Total Bridge Length:	0.044 Miles	Letting Date:	01/03/20
Total Proposal Length:	0.088 Miles	Contract Execution Days:	
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	90

Proposal Budget Estimate: \$838,504.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of full removal and replacement of the existing structural steel coating system, cleaning and coating of Class-V Finish to concrete surfaces on SR-84 over south fork of New River Bridge No. 860008 in Broward County.

Pre-Qualified: Contractor must be pre-qualified.

Performance Bond: A Contract / Performance bond is required for this project

Call Order: 003 Proposal: E4T89

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0465- 3- 50	MOVABLE BRIDGE COUNTERWEIGHT, ADJUST	EA	3.000
	0465- 20-	MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR (43214615201 860008)	LS	1.000
	0465- 21-	MOVABLE BRIDGE OPERATOR	DA	89.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43214615201 860008)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43214615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43214615201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43214615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	7,668.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	20.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,752.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,728.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	24.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	212.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	718.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	20.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	20.000
	0536- 73-	GUARDRAIL REMOVAL	LF	20.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43214615201)	LS	1.000