

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 04211203 Call Order: 003 Proposal: E4V57 District:04

Counties: BROWARD

Road Name: BROWARD COUNTY PUSH BUTTON CONTRACT TRAFFIC OPS - ROADWAY

Limits: Midpoint

Project(s): 42924945201(\*)

Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 730

Total Bridge Length: 0.000 Miles Letting Date: 12/03/21

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time:

Proposal Budget Estimate: \$1,000,000.00

Please read the full advertisement

**Description:**

The Improvements, implemented by individual Task Work Order(s)/Work Document(s) under this Contract, consist of, but are not limited to, asphalt (milling and resurfacing, miscellaneous), concrete (removals, gravity wall, curb, gutter, traffic separator, sidewalk, driveways), earthwork, handrail (pipe), guardrail (removal), signing (single post, multi-post, panel, work zone), pavement markings (tubular marker, raised marker, object marker, detectable, paver, painted, thermoplastic), conduit, pull/splice box, strain pole (removal), lighting (conductors, pole complete), drainage (inlets), electrical (service wire, load center), utilities adjustments (valve box), and sod throughout Broward County.

**WORK DRIVEN CONTRACT:** The award amount shall be based on the budgeted amount of \$1,000,000.00 and not the contractors bid total over the two (2) year term of the contract.

- The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed.
- For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

**PRE-QUALIFIED:** Contractor must be pre-qualified.

**PERFORMANCE BOND:** A Contract / Performance bond is required for this project.

**COMMERCIAL GENERAL LIABILITY INSURANCE:**

The limits of coverage shall not be less than \$1,000,000 for each occurrence and not less than a \$5,000,000 annual general aggregate, inclusive of amounts provided by an umbrella or excess policy. The limits of coverage described herein shall apply fully to the work or operations performed under the Contract, and may not be shared with or diminished by claims unrelated to the contract. The policy/ies and coverage described herein may be subject to a deductible. Pay all deductibles as required by the policy. No policy/ies or coverage described herein may contain or be subject to a Retention or a Self-Insured Retention.

**SPECIAL NOTES and REQUIREMENTS (List/Explain)**

- The Improvements, implemented by individual Task Work Order(s)/Work Document(s) under this Contract, consist of, but are not limited to, roadway construction, intersection improvements, roadway signing and pavement marking throughout Broward County.
- Original contract time is 730 days. This is not a renewable contract.
- Maximum Dollar amount for this contract is \$1,000,000.00.
- The Summary of Pay Items for each project is listed in the plans.
- The contractor must be pre-qualified under "Flexible Paving".
- Pre-Bid Meeting is not required.
- The duration of each Work Order under this contract will be per Contract Documents.

**Call Order: 003 Proposal: E4V57**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	60.000
	0102- 60-	WORK ZONE SIGN	ED	3,000.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	300.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	300.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,000.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	400.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	5.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	300.000
	0104- 10- 3	SEDIMENT BARRIER	LF	650.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	25.000
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	0.500
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	200.000
	0120- 1-	REGULAR EXCAVATION	CY	400.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	200.000
	0120- 6-	EMBANKMENT	CY	300.000
	0160- 4-	TYPE B STABILIZATION	SY	100.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	100.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	200.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	200.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	400.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,500.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	30.000
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	30.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	70.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	70.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	70.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	70.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	70.000
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	70.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	40.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	40.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	2.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	2.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	2.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	2.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	2.000
	0425- 6-	VALVE BOXES, ADJUST	EA	5.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	20.000

ALT	Item	Description	Unit	Quantity
	0430-173-124	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 24", GUTTER DRAIN	LF	20.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	45.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	400.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	400.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	100.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	300.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	100.000
	0523- 1-	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	120.000
	0523- 2-	PATTERNED PAVEMENT, NON-VEHICULAR AREAS	SY	120.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	75.000
	0527- 2-	DETECTABLE WARNINGS	SF	150.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	500.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	500.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	5.000
	0536- 73-	GUARDRAIL REMOVAL	LF	100.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	5.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	5.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	5.000
	0538- 1-	GUARDRAIL RESET	LF	100.000
	0544- 2- 1	CRASH CUSHION, TL-2, NARROW	EA	2.000
	0544- 2- 2	CRASH CUSHION, TL-2, WIDE	EA	2.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	2.000
	0544- 3- 2	CRASH CUSHION, TL-3, WIDE	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	800.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	300.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	300.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	100.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	5.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	50.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	50.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	4.000
	0643-600-	STRAIN POLE, WOOD, REMOVE	EA	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	5.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	5.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	5.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	3.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	300.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	300.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	300.000
	0715- 4- 14	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT	EA	2.000

ALT	Item	Description	Unit	Quantity
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	3.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	3.000
	0715- 4- 71	LIGHT POLE COMPLETE, REMOVE POLE, FOUNDATION REMAINS	EA	3.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	15.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	5.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	5.000
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	AS	2.000
	0700- 1- 22	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013, 12-20 SF	AS	2.000
	0700- 1- 32	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	12.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	15.000
	0700- 2- 11	MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	1.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	1.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	4.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	3.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	5.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	4.000
	0700- 3-503	SIGN PANEL, RELOCATE, 21-30 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	5.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	4.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	3.000
	0704- 1- 1	TUBULAR MARKER, DURABLE, 36" WHITE POST	EA	5.000
	0704- 1- 2	TUBULAR MARKER, DURABLE, 36" YELLOW POST	EA	5.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	10.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	10.000
	0705- 11- 6	DELINEATOR, REPLACE DELINEATOR ON EXISTING BARRIER	EA	10.000
	0705- 11- 11	DELINEATOR POST, FURNISH & INSTALL ON EXISTING BASE	EA	5.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	300.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.250
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.250
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	300.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	150.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.250

ALT	Item	Description	Unit	Quantity
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.100
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	20.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.250
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	50.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.250
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	200.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	200.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	600.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.100
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	20.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	20.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	200.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.100
	0711- 12-160	THERMOPLASTIC, REFURBISH, WHITE, MESSAGE	EA	5.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	5.000
	0711- 12-231	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	GM	0.250
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	200.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	600.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	10.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	15.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	5.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.250
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.250
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.250
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 1C-30 SKIP OR 3-9 LANE DROP	GM	0.100
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.250
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.250