

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04210507 Call Order: 008 Proposal: E4U49 District:04
Counties: BROWARD
Road Name: SR-A1A OVER HILLSBORO INLET BRIDGE# 860011 - BRIDGE-REPAIR
Limits: 86050000
Project(s): 44145815201(*) Federal Aid No: N/A
Total Roadway Length: 0.063 Miles Contract Days: 147
Total Bridge Length: 0.062 Miles Letting Date: 05/07/21
Total Proposal Length: 0.125 Miles Contract Execution Days:
Special Start Date: N/A
Aquis/Flexible Start Time: 60
Proposal Budget Estimate: \$1,637,623.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of , but are not limited to, bridge scour countermeasures (articulating concrete-block revetment system), replacement of submarine cable assembly, and replacement of bicycle plates, along State Road A1A at Bridge Number 860011 (over Hillsboro Inlet) for 0.063 miles in the City of Pompano Beach and the Town of Hillsboro Beach, Broward County..

Pre-Qualified: Contractor need to be pre-qualified.

Performance Bond: A Contract / Performance bond is required for this project.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 008 Proposal: E4U49

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES	LB	3,402.000
	0465- 3- 50	MOVABLE BRIDGE COUNTERWEIGHT, ADJUST	EA	1.000
	0465- 20-	MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR (44145815201)	LS	1.000
	0465- 21-	MOVABLE BRIDGE OPERATOR	DA	147.000
	0508- 73- 1	SUBMARINE CABLE ASSEMBLY, FURNISH & INSTALL (44145815201)	LS	1.000
	0508- 73- 4	SUBMARINE CABLE ASSEMBLY, REMOVE (44145815201)	LS	1.000
	0530- 4- 9	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 9"	SY	994.000
	0530- 74-	BEDDING STONE	TN	1,660.700
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44145815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44145815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,236.000
	0102- 61-	BUSINESS SIGN	EA	1.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,056.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,236.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	44.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	322.000
	0102-115-	TYPE III BARRICADE	ED	309.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	686.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44145815201)	LS	1.000
Section 0003 Signing				
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.030