

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04210507 Call Order: 009 Proposal: E4U70 District:04

Counties: PALM BEACH

Road Name: SR-786/PGA BLVD OVER INTERACOASTAL WATER(ICWW)-BRIDGE-REPAIR

Limits: 93001000

Project(s): 44147015201(*)

Federal Aid No: N/A

Total Roadway Length: 0.144 Miles Contract Days: 185

Total Bridge Length: 0.073 Miles Letting Date: 05/07/21

Total Proposal Length: 0.217 Miles Contract Execution Days:

Special Start Date: N/A

Aquis/Flexible Start Time: 60

Proposal Budget Estimate: \$1,813,759.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of but are not limited to, scour countermeasures (riprap, articulating concrete block, bedding stone), submarine cable (removal, installation), and moveable bridge (operation, preventative maintenance, functional checkout, electrical rehabilitation), along State Road 786 (PGA Boulevard) over Intracoastal Waterway (Bridge No. 930106 and Bridge No. 930349) for 0.072 miles in the City of Palm Beach Gardens, Palm Beach County.

Pre-Qualified: Contractor need to be pre-qualified.

Performance Bond: A Contract / Performance bond is required for this project.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 009 Proposal: E4U70

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0465- 20-	MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR (44147015201 930106)	LS	1.000
	0465- 21-	MOVABLE BRIDGE OPERATOR (44147015201 930106)	DA	185.000
	0465- 71- 3	MOVABLE BRIDGE FUNCTIONAL CHECKOUT, PHASE C (44147015201 930106)	LS	1.000
	0508- 4-	MOVABLE BRIDGE ELECTRICAL EQUIPMENT, REHABILITATION (44147015201 930106)	LS	1.000
	0508- 73- 1	SUBMARINE CABLE ASSEMBLY, FURNISH & INSTALL (44147015201 930106)	LS	1.000
	0508- 73- 4	SUBMARINE CABLE ASSEMBLY, REMOVE (44147015201 930106)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44147015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44147015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	430.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,021.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,494.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	43.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	57.000
	0102-115-	TYPE III BARRICADE	ED	86.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,744.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	310.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	368.000
	0530- 4- 4	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 4"	SY	4,488.000
	0530- 74-	BEDDING STONE	TN	272.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44147015201)	LS	1.000