

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 04220701      Call Order: 002      Proposal: E4U88      District:04

Counties: ST LUCIE

Road Name: SAVANNAS PRESERVE STATE PARK GAP

Limits: Midpoint

Project(s): 43999925201(\*)      Federal Aid No: N/A

Total Roadway Length: 0.000 Miles      Contract Days: 607

Total Bridge Length: 0.000 Miles      Letting Date: 07/01/22

Total Proposal Length: 0.000 Miles      Contract Execution Days:  
Special Start Date: N/A  
Aquis/Flexible Start Time: 30

Proposal Budget Estimate: \$8,641,273.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of a shared-used path, which include but are not limited to, monitor existing structures (inspection, settlement), concrete (removal, sidewalk), signing, pavement markings (detectable warnings), and sod along Savannas SUNTRAIL from Walton Road to Lennard Road for 6.559 miles in St. Lucie County.

PRE-QUALIFIED: Contractor needs to be pre-qualified.

PERFORMANCE BOND: A Contract / Performance bond is required for this project.

**COMMERCIAL GENERAL LIABILITY INSURANCE:**

The limits of coverage shall not be less than \$1,000,000 for each occurrence and not less than a \$5,000,000 annual general aggregate, inclusive of amounts provided by an umbrella or excess policy. The limits of coverage described herein shall apply fully to the work or operations performed under the Contract, and may not be shared with or diminished by claims unrelated to the contract. The policy/ies and coverage described herein may be subject to a deductible. Pay all deductibles as required by the policy. No policy/ies or coverage described herein may contain or be subject to a Retention or a Self-Insured Retention.

**WORKERS COMPENSATION INSURANCE**

PREVENTION, CONTROL, AND ABATEMENT OF EROSION AND WATER POLLUTION : Please read from the Specs Package Section 104.

**Call Order: 002 Proposal: E4U88**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43999925201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43999925201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,463.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,035.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	6,070.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,863.000
	0104- 10- 3	SEDIMENT BARRIER	LF	70,468.000
	0107- 1-	LITTER REMOVAL	AC	13.310
	0107- 2-	MOWING	AC	6.770
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43999925201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43999925201)	LS	1.000

**Call Order: 002 Proposal: E4U88**

ALT	Item	Description	Unit	Quantity
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	12.300
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	5.000
	0110- 21-	TREE PROTECTION BARRIER	LF	11,355.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	670.000
	0110- 23-	TREE REMOVAL	EA	43.000
	0120- 1-	REGULAR EXCAVATION	CY	3,583.000
	0120- 4-	SUBSOIL EXCAVATION	CY	79.600
	0120- 6-	EMBANKMENT	CY	8,856.000
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	55,142.000
	0160- 4-	TYPE B STABILIZATION	SY	39,286.000
	0285-705-	OPTIONAL BASE, BASE GROUP 05	SY	1,210.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	22.300
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	2,672.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	797.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	126.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	114.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	18.000
	0455- 2- 12	TREATED TIMBER PILING FOR PEDESTRIAN BOARDWALK, PROJECT 439999-2-52-01	LF	13,383.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	109.200
	0519- 78-	BOLLARDS	EA	40.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	35,724.000
	0527- 2-	DETECTABLE WARNINGS	SF	85.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	1,102.600
	0550- 10-118	FENCING, TYPE A, 0.0-5.0', TYPE A STANDARD, RESET EXISTING	LF	67.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	27,664.000
	0999- 16-	PARTNERING, DO NOT BID (43999925201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43999925201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	6.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	2.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	50.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	91.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.460
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.060