

Call Order: 004 Proposal: E4V59

ALT	Item	Description	Unit	Quantity
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44136015201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44136015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44136015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	637.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	29.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	119.000
	0110- 23-	TREE REMOVAL	EA	57.000
	0120- 1-	REGULAR EXCAVATION	CY	1,655.000
	0120- 6-	EMBANKMENT	CY	1,631.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,274.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	7,573.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	98.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	59,351.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	15,821.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	5,521.400
	0425- 1-910	INLETS, CLOSED FLUME	EA	8.000
	0425- 82-	REPLACE GRATE	EA	2.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	51.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	4,769.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,068.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,312.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	2,454.000
	0527- 2-	DETECTABLE WARNINGS	SF	88.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,723.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,844.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	13.702
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	13.686
	0999- 16-	PARTNERING, DO NOT BID (44136015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44136015201)	LS	1.000
Section 0002 Signing				
	0654- 2- 22	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	16.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	38.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	31.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	30.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	973.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44136015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	746.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	29.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.009

Call Order: 004 Proposal: E4V59

ALT	Item	Description	Unit	Quantity
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	430.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	37.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	37.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	6.835
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.847
Section 0003 Utilities				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	52.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (44136015202)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (44136015601)	LS	1.000
	1080- 21-400	UTILITY FIXTURE, VALVE/METER BOX, RELOCATE	EA	1.000
	1080- 21-500	UTILITY FIXTURE, VALVE/METER BOX, ADJUST	EA	420.000
	1644-700-	FIRE HYDRANT, ADJUST & MODIFY	EA	15.000