

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 04231201 Call Order: 003 Proposal: E4X08-R0 District:04

Counties: DIST/ST-WIDE

Road Name: TREASURE COAST COUNTIES DRAINAGE - ROUTINE MAINTENANCE

Limits: Midpoint

Project(s): 44103947201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	12/01/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	13

Proposal Budget Estimate: \$200,000.00

Please read the full advertisement

Description:

The work under this Contract consists of all labor, materials, equipment and incidentals necessary for repair, replacement, construction and other work related to drainage systems along State owned roadways in Martin, St. Lucie, and Indian River Counties.

•ADVERTISED ESTIMATE: The award amount and contract performance bond shall be based on the Department s advertised estimate amount of \$200,000.00 and not the contractors bid total.

•PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY2023-24 (SECTION 7-13) FOR INSURANCE LIMITS.

Call Order: 003 Proposal: E4X08-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	40.000
	0102- 60-	WORK ZONE SIGN	ED	100.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	100.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	100.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	100.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	25.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102-115-	TYPE III BARRICADE	ED	100.000
	0104- 10- 3	SEDIMENT BARRIER	LF	25.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	50.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	25.000
	0120- 1-	REGULAR EXCAVATION	CY	100.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	50.000
	0120- 6-	EMBANKMENT	CY	250.000
	0120- 9- 1	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH UP TO 15'	LF	250.000
	0120- 9- 2	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH 15-30'	LF	250.000
	0120- 9- 3	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH GREATER THAN 30'	LF	100.000

Call Order: 003 Proposal: E4X08-R0

ALT	Item	Description	Unit	Quantity
	0120- 10- 23	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH GREATER THAN 30'	LF	100.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	10.000
	0145- 1-	GEOSYNTHETIC REINFORCED SOIL SLOPE	SF	499.100
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	25.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	25.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	2.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	25.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	1.000
	0425- 2-110	MANHOLES, REPAIR	EA	3.000
	0425- 4-	INLETS, ADJUST	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0430- 96-	DRAINAGE PIPE REPAIR- CONCRETE COLLAR AT JOINT	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	20.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	20.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	5.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	5.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	5.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	5.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	25.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	50.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	5.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	4.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	1.000
	0430-984-141	MITERED END SECTION , OPTIONAL ROUND, 48" SD	EA	1.000
	0430-991- 1	MITERED END SECT, REPLACE SLAB- MAINTENANCE USE ONLY	CY	5.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	35.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	4.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	50.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	49.000
	0527- 2-	DETECTABLE WARNINGS	SF	26.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	20.000
	0530- 74-	BEDDING STONE	TN	5.000

Call Order: 003 Proposal: E4X08-R0

ALT	Item	Description	Unit	Quantity
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.250
	E110- 2-	CLEARING & GRUBBING	AC	4.000
	E120- 10- 1	CLEAN AND RESHAPE DITCH (SPREAD)	LF	100.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	100.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	9.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	2.000
	E575- 1-	SODDING	SY	500.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	25.000
	E710- 11-121	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	LF	20.390
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	20.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	20.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	20.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	21.000