

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04230203 Call Order: 007 Proposal: E4W30-R0 District:04

Counties: BROWARD

Road Name: BROWARD NPDES CORRECTIVE ACTIONS - ROUTINE MAINTENANCE

Limits: Midpoint

Project(s): 42833367201(*)

Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 365

Total Bridge Length: 0.000 Miles Letting Date: 02/03/23

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 13

Proposal Budget Estimate: \$450,000.00

Please read the full advertisement

Description:

The work within this Contract consists of providing the means and methods to resolve maintenance issues related to the States drainage system and to provide corrective actions for National Pollution Elimination Discharge Systems NPDES related inspection deficiencies to assets servicing the State Road System throughout Broward County.

MAXIMUM LIMITING CONTRACT: The award amount and contract performance bond shall be based on maximum limiting budgeted amount of \$450,000.00 and not the contractors bid total.

REQUIRED SUBMITTAL WITH BID: Drainage Experience Form 850-070-05 must be submitted with the bid.

PERFORMANCE BOND: A Contract or Performance bond is required for this project.

GENERAL LIABILITY: The limits of coverage shall not be less than \$1,000,000 for each occurrence and not less than a \$5,000,000 annual general aggregate, inclusive of amounts provided by an umbrella or excess policy. The limits of coverage described herein shall apply fully to the work or operations performed under the Contract and may not be shared with or diminished by claims unrelated to the contract. The policy and coverage described herein may be subject to a deductible. Pay all deductibles as required by the policy. No policy or coverage described herein may contain or be subject to a Retention or a Self-Insured Retention.

Call Order: 007 Proposal: E4W30-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	50.000
	0120- 1-	REGULAR EXCAVATION	CY	140.000
	0120- 4-	SUBSOIL EXCAVATION	CY	10.000
	0120- 6-	EMBANKMENT	CY	50.000
	0120- 10- 21	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH UP TO 15'	LF	50.000
	0120- 10- 22	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH 15-30'	LF	50.000
	0121- 70-	FLOWABLE FILL	CY	25.000
	0173- 77- 1	SUBSURFACE PRESSURE GROUTING, SAND CEMENT	CY	25.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	10.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	3.000
	0425- 4-	INLETS, ADJUST	EA	7.000
	0425- 5-	MANHOLE, ADJUST	EA	23.000
	0425- 82-	REPLACE GRATE	EA	2.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	50.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	50.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	50.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	1.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	50.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	50.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	50.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	100.000
	0524- 4- 1	CLEANING & SEALING RANDOM CRACKS IN EXISTING CONCRETE SLOPE PAVEMENT	LF	46.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	50.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	8.000
	E110- 2-	CLEARING & GRUBBING	AC	3.500
	E110- 30-	LITTER REMOVAL	AC	5.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	20,000.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	180.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	6.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	10.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	250.000
	E425- 73- 6	SECURE MANHOLE / INLET LIDS	EA	6.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	15,000.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	5,000.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	5,000.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	485.000
	E524- 1- 1	CONCRETE DITCH PAVEMENT REPAIR	CY	115.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	24,505.000
	E575- 1- 4	SODDING, ST AUGUSTINE	SY	2,000.000
	E575- 1- 8	SODDING, BAHIA	SY	2,000.000
	E577- 70-	SHOULDER REWORK	SY	7,000.000