



**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 005 Proposal: E4W60-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 TRAFFIC CONTROL DEVICES CONTROL (MH)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	325.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	20.000
	0110- 3- 4	REMOVAL OF EXISTING SAND CEMENT RIPRAP - FOR PUSH BUTTON/MAINTENANCE CONTRACTS ONLY	SF	25.000
	0110- 71- 1	BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL	LF	1.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	5.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	300.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	10.000
	0400- 2- 5	CONCRETE CLASS II, BRIDGE SUBSTRUCTURE	CY	10.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	10.000
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	10.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	10.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	300.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	1,000.000
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	5.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	50.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	10.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	250.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	25.000
	0457- 1- 22	STANDARD INTEGRAL PILE JACKET, STRUCTURAL, 16.1 to 30.0"	LF	1.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	1.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	1,350.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	25.000
	0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES	LB	5.000
	0460- 94-	STRUCTURAL STEEL REPAIR- WELDS	LF	5.000
	0471- 1- 1	FENDER SYSTEM,PLASTIC MARINE LUMBER,REINFORCED	MB	1.000
	0471- 1- 2	FENDER SYSTEM,PLASTIC MARINE LUMBER, NON-REINFORCED	MB	1.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	25.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	75.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	25.000
	0561- 2-	COATING EXISTING STRUCTURAL STEEL	SF	50.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	1.000
	E101- 74-	MOBILIZATION (SPECIALIZED)	DA	3.000
	E460- 19- 1	ARMOR ANGLE (REMOVE)	LF	10.000
	E460- 82-	BOLT TIGHTENING	EA	5.000
	E534- 72- 3	SOUND/NOISE BARRIER ANGLE MEMBERS, INSTALL	EA	110.000