

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	04230901	Call Order: 006	Proposal: E4W91-R0	District:04
Counties:	BROWARD			
Road Name:	BROWARD COUNTY PAVEMENT STRIPING			
Limits:	Midpoint			
Project(s):	43468237201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	09/01/23	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	13	

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

The work under this Contract consists of the refurbishment of existing thermoplastic pavement markings, as well as the removal and installation of standard thermoplastic pavement markings along the State Highway System in Broward County.

- **PERFORMANCE BOND:** A Contract / Performance bond is required for this project.
- **ADVERTISED ESTIMATE:** The award amount and contract performance bond shall be based on the Departments advertised estimate amount of \$500,000.00 and not the contractors bid total
- **REQUIRED SUBMITTAL WITH BID:** Pavement Markings Experience Form 850-070-06 must be submitted with the bid.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY2023-24 (SECTION 7-13) FOR INSURANCE: LIMITS

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 006 Proposal: E4W91-R0

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)				
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	3.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,000.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,000.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	6,000.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	50.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	500.000
	0711- 12-101	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	GM	50.000
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8" FOR MAINTENANCE USE	LF	5,000.000
	0711- 12-123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12" FOR CROSS WALK OR ROUNDABOUT- MAINTENANCE USE ONLY	LF	2,000.000
	0711- 12-124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON, MAINTENANCE USE ONLY	LF	500.000
	0711- 12-125	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 24" FOR STOP LINE OR CROSSWALK, MAINTENANCE USE ONLY	LF	500.000
	0711- 12-131	THERMOPLASTIC, REFURBISHMENT, WHITE, SKIP, 6"	GM	50.000
	0711- 12-141	THERMOPLASTIC, REFURBISHMENT, WHITE, 2-4 DOTTED GUIDELINE / 6-10 GAP EXTENSION, 6", MAINTENANCE USE ONLY	GM	9.500
	0711- 12-160	THERMOPLASTIC, REFURBISH, WHITE, MESSAGE	EA	12.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	30.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	20.000
	0711- 12-221	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6" MAINTENANCE USE ONLY	LF	2,000.000
	0711- 12-224	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON, MAINTENANCE USE ONLY	LF	200.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	100.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	235.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	136.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	136.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.000
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.000
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 1C -30 SKIP OR 3-9 LANE DROP	GM	1.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	40,000.000
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	1,000.000