

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 04241206 Call Order: 006 Proposal: E4X88-R0 District:04

Counties: BROWARD

Road Name: BROWARD COUNTY PUSHBUTTON DESILTING - ROUTINE MAINTENANCE

Limits: Midpoint

Project(s): 45341117201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	12/06/24
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	13

Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

Description:

The work under this Contract consists of providing all labor, equipment, materials and incidentals necessary for the cleaning, evaluating, repairing the drainage systems on State Roadways in Broward County, and collecting the associated video and Geographic Information system (GIS) data.

•ADVERTISED ESTIMATE: The award amount and contract performance bond shall be based on the Department s advertised estimate amount of \$400,000.00 and not the contractor s bid total.

•PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2024-25 (SECTION 7-13) FOR INSURANCE LIMITS.

Call Order: 006 Proposal: E4X88-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	10.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	24.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	6.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	1,200.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	30,000.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	4,800.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	2,600.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	600.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	300.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	650.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	240.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	96.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	3,600.000
	E999- 3- 1	HYDRAULIC PUMP, 4"	HR	40.000
	E999- 3- 2	HYDRAULIC PUMP, 6"	HR	40.000