

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 04240202      Call Order: 007      Proposal: E4X34-R0      District:04

Counties: DIST/ST-WIDE

Road Name: TREASURE COAST NPDES CORRECTIVE ACTIONS

Limits: Midpoint

Project(s): 42833567201(\*)      Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	02/02/24
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	13

Proposal Budget Estimate: \$250,000.00

Please read the full advertisement

**Description:**

The work under this Contract consists of all labor, equipment, materials and incidentals necessary to rehabilitate any part of the NPDES/drainage system assets, remove and dispose of any type of blockage inside of any part of the storm drainage system to provide maximum drainage capacity of the Department s storm water system in Martin, St. Lucie, and Indian River Counties.

•ADVERTISED ESTIMATE: The award amount and contract performance bond shall be based on the Department s advertised estimate amount of \$250,000.00 and not the contractors bid total.

•PERFORMANCE BOND: A Contract / Performance bond is required for this project.

•REQUIRED SUBMITTAL WITH BID: Experience Form Drainage Repair 850-070-05 must be submitted with the bid.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2023-24 (SECTION 7-13) FOR INSURANCE LIMITS.

**Call Order: 007 Proposal: E4X34-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	15.000
	0102- 60-	WORK ZONE SIGN	ED	200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	150.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	20.000
	0102-115-	TYPE III BARRICADE	ED	150.000
	0104- 10- 3	SEDIMENT BARRIER	LF	20.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	50.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	68.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	20.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	25.000
	0120- 1-	REGULAR EXCAVATION	CY	122.280
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	100.000
	0120- 6-	EMBANKMENT	CY	100.000
	0120- 9- 1	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH UP TO 15'	LF	500.000
	0120- 9- 2	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH 15-30'	LF	500.000
	0120- 9- 3	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH GREATER THAN 30'	LF	250.000

**Call Order: 007 Proposal: E4X34-R0**

ALT	Item	Description	Unit	Quantity
	0120- 10- 23	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH GREATER THAN 30'	LF	200.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	25.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	15.000
	0425- 4-	INLETS, ADJUST	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	3.000
	0430- 96-	DRAINAGE PIPE REPAIR- CONCRETE COLLAR AT JOINT	EA	6.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	20.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	20.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	10.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	5.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	5.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	50.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	50.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	3.000
	0430-991- 1	MITERED END SECT, REPLACE SLAB- MAINTENANCE USE ONLY	CY	5.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	50.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	10.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	25.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	25.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	25.000
	0530- 74-	BEDDING STONE	TN	4.000
	E110- 2-	CLEARING & GRUBBING	AC	5.000
	E120- 10- 1	CLEAN AND RESHAPE DITCH (SPREAD)	LF	100.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	450.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	5.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	5.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	1,000.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	1,000.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	500.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	500.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	440.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	100.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	100.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	100.000
	E431- 1- 24	PIPE LINER, CURED IN PLACE, 49-60"	LF	10.000
	E431- 1- 25	PIPE LINER, CURED IN PLACE, 61" AND GREATER	LF	10.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	1,000.000
	E575- 1-	SODDING	SY	1,567.000