

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 04240105      Call Order: 003      Proposal: E4X09      District:04

Counties: DIST/ST-WIDE

Road Name: TREASURE COAST PRIMARY ASPHALT REPAIR - ROUTINE MAINTENANCE

Limits: Midpoint

Project(s): 42977467201(\*)      Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	730
Total Bridge Length:	0.000 Miles	Letting Date:	01/05/24
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	13

Proposal Budget Estimate: \$150,000.00

Please read the full advertisement

**Description:**

The work under this Contract consists of all materials, labor, equipment and incidentals necessary to perform spot asphalt repair by milling and paving, placing pavement markings and the installation of traffic loops on State roads in Martin, St Lucie, and Indian River Counties.

•ADVERTISED ESTIMATE: The award amount and contract performance bond shall be based on the Department s advertised estimate amount of \$150,000.00 and not the contractors bid total.

•PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY2023-24 (SECTION 7-13) FOR INSURANCE LIMITS.

**Call Order: 003 Proposal: E4X09**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)</b>				
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	175.574
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	235.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	235.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	267.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	267.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	131.410
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	80.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	75.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	75.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	2.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	200.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	200.000

**Call Order: 003 Proposal: E4X09**

ALT	Item	Description	Unit	Quantity
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	25.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	25.000
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	100.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	100.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	100.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	100.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	20.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	200.000
	0711- 12-141	THERMOPLASTIC, REFURBISHMENT, WHITE, 2-4 DOTTED GUIDELINE / 6-10 GAP EXTENSION, 6", MAINTENANCE USE ONLY	GM	1.000
	0711- 12-222	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 8" MAINTENANCE USE ONLY	LF	1,000.000
	0711- 12-241	THERMOPLASTIC, REFURBISHMENT, YELLOW 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" MAINT USE ONLY	GM	1.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	100.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	50.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	170.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	2.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	400.000
	E710- 11-121	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	LF	900.000
	E710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	LF	899.000
	E710- 11-221	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	LF	899.000
	E710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	LF	900.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	900.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	1,000.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	1,000.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	894.550