

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04240906 Call Order: 004 Proposal: E4X24 District:04
Counties: PALM BEACH
Road Name: I-95 BRIDGE VIA DUCT FROM 6TH AVE S TO LAKE WORTH RD PB
Limits: 93220000
Project(s): 44931815201(*) Federal Aid No: N/A
Total Roadway Length: 1.020 Miles Contract Days: 230
Total Bridge Length: 1.009 Miles Letting Date: 09/06/24
Total Proposal Length: 2.029 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 90
Proposal Budget Estimate: \$5,136,144.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, rehabilitation of bridge deck expansion joints, pore joint with backer rod, and epoxy overlay for sealing and high-friction surface treatment on concrete bridge decks on Bridge Numbers 930510, 930511, 930261, and 930262, along State Road 9 (I-95) for 0.436 miles in Palm Beach County.

PRE-QUALIFIED: Contractor must be pre-qualified.

PERFORMANCE BOND: A Contract / Performance bond is required for this project.

MARINE GENERAL LIABILITY INSURANCE– per Project Manager, not required.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2024-25 (SECTION 7-13) FOR INSURANCE LIMITS.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 004 Proposal: E4X24

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0403- 1-100	EPOXY CONCRETE OVERLAY FOR CONCRETE BRIDGE DECKS	SY	43,845.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	5,790.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	403.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44931815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44931815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,205.000
	0102- 60-	WORK ZONE SIGN	ED	7,566.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	25,896.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	494.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	732.000
	0102-115-	TYPE III BARRICADE	ED	990.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	528.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	528.000
	0999- 16-	PARTNERING, DO NOT BID (44931815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44931815201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,038.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44931815201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	906.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,460.000