

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	04251107	Call Order: 002	Proposal: E4Y31-R0	District:04
Counties:	BROWARD			
Road Name:	BROWARD PAVEMENT MARKINGS & STRIPING HAND LINE			
Limits:	Midpoint			
Project(s):	43978157201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	11/07/25	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	13	

Proposal Budget Estimate: \$300,000.00

Please read the full advertisement

Description:

The work under this Contract consists of providing all labor, materials, equipment and incidentals necessary to install, remove and replace thermoplastic pavement markings at various locations within Broward County.

The summary of pay items for this project is listed in the Bid Price Proposal.

•PRE-QUALIFIED: Contractor does not need to be pre-qualified.

•PERFORMANCE BOND: A Contract / Performance bond is required for this project.

•ADVERTISED ESTIMATE: The award amount and contract performance bond shall be based on the Department s advertised estimate amount of \$300,000.00 and not the contractor s bid total.

•REQUIRED SUBMITTAL WITH BID: Experience Form Pavement Markings 850-070-06.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2025-26 (SECTION 7-13) FOR INSURANCE LIMITS.

Call Order: 002 Proposal: E4Y31-R0

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT SYMBOLS (SF)				
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	7,000.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	850.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,750.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	40.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	200.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	150.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.500
	0711- 12-121	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6" FOR MAINTENANCE USE	LF	100.000
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8"	LF	1,200.000

Call Order: 002 Proposal: E4Y31-R0

ALT	Item	Description	Unit	Quantity
	0711- 12-123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12" FOR CROSS WALK OR ROUNDABOUT	LF	2,000.000
	0711- 12-124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	100.000
	0711- 12-125	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 24" FOR STOP LINE OR CROSSWALK	LF	2,000.000
	0711- 12-141	THERMOPLASTIC, REFURBISHMENT, WHITE, 2-4 DOTTED GUIDELINE / 6-10 GAP EXTENSION, 6", MAINTENANCE USE ONLY	GM	1.000
	0711- 12-160	THERMOPLASTIC, REFURBISH, WHITE, MESSAGE	EA	20.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	200.000
	0711- 12-221	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6" MAINTENANCE USE ONLY	LF	100.000
	0711- 12-224	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON, MAINTENANCE USE ONLY	LF	100.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	300.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	50.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	45.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	45.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	20.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	10,000.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.500
	0713-103-141	PERMANENT TAPE, WHITE, 6-10 SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.500
	0713-103-173	PERMANENT TAPE, WHITE, 3-9 DOTTED, 12" WIDE, FOR CONCRETE SURFACES	GM	0.500
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.500
	0713-103-271	PERMANENT TAPE, YELLOW, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.500
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.500
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	2,000.000