

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

|                        |                                                             |                            |                 |             |
|------------------------|-------------------------------------------------------------|----------------------------|-----------------|-------------|
| Letting:               | 04251003                                                    | Call Order: 001            | Proposal: E4X91 | District:04 |
| Counties:              | BROWARD                                                     |                            |                 |             |
| Road Name:             | COUNTYWIDE SONOVOID SLAB BRIDGE REHAB - BRIDGE-REPAIR/REHAB |                            |                 |             |
| Limits:                | 86016000                                                    |                            |                 |             |
| Project(s):            | 44924315201(*)                                              | Federal Aid No: N/A        |                 |             |
| Total Roadway Length:  | 0.040 Miles                                                 | Contract Days:             | 243             |             |
| Total Bridge Length:   | 0.041 Miles                                                 | Letting Date:              | 10/03/25        |             |
| Total Proposal Length: | 0.081 Miles                                                 | Contract Execution Days:   | 10              |             |
|                        |                                                             | Special Start Date:        | N/A             |             |
|                        |                                                             | Aquis/Flexible Start Time: | 45              |             |

Proposal Budget Estimate: \$2,080,559.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of sonovoid slab bridge rehabilitation, addressing independent slab movement between the adjacent slab units using ultra-high performance concrete to repair the longitudinal joints between the adjacent slab units, and other incidental work, for Bridge Nos. 860001 and 860591, in Broward County.

- PRE-QUALIFIED: Contractor must be pre-qualified.
- PERMITS LINK: Cerberus Web Client
- PERFORMANCE BOND: A Contract / Performance bond is required for this project

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2025-26 (SECTION 7-13) FOR INSURANCE LIMITS.

**Call Order: 001 Proposal: E4X91**

| ALT                            | Item         | Description                                                               | Unit | Quantity   |
|--------------------------------|--------------|---------------------------------------------------------------------------|------|------------|
| <b>Section 0001 Structures</b> |              |                                                                           |      |            |
|                                | 0110- 12- 1  | HYDRODEMOLITION, REMOVAL OF DECK SURFACE                                  | SY   | 142.000    |
|                                | 0415- 1- 4   | REINFORCING STEEL - BRIDGE SUPERSTRUCTURE                                 | LB   | 2,098.000  |
|                                | 0458- 1- 21  | BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD | LF   | 723.000    |
|                                | 0458- 2-     | POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT                            | CF   | 154.300    |
|                                | 0918-349-100 | ULTRA HIGH PERFORMANCE CONCRETE (UHPC)                                    | CY   | 27.500     |
| <b>Section 0002 Roadway</b>    |              |                                                                           |      |            |
|                                | 0101- 1-     | MOBILIZATION (44924315201)                                                | LS   | 1.000      |
|                                | 0102- 1-     | MAINTENANCE OF TRAFFIC (44924315201)                                      | LS   | 1.000      |
|                                | 0102- 14-    | TRAFFIC CONTROL OFFICER                                                   | HR   | 44.000     |
|                                | 0102- 60-    | WORK ZONE SIGN                                                            | ED   | 8,254.000  |
|                                | 0102- 61-    | BUSINESS SIGN                                                             | EA   | 4.000      |
|                                | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                    | ED   | 65,352.000 |
|                                | 0102- 74- 8  | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)    | FD   | 2,000.000  |
|                                | 0102- 76-    | ARROW BOARD / ADVANCE WARNING ARROW PANEL                                 | ED   | 856.000    |
|                                | 0102- 99-    | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                               | ED   | 639.000    |
|                                | 0102-104-    | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION                     | ED   | 854.000    |

**Call Order: 001 Proposal: E4X91**

| ALT                         | Item         | Description                                                                          | Unit | Quantity  |
|-----------------------------|--------------|--------------------------------------------------------------------------------------|------|-----------|
|                             | 0102-107- 1  | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION                            | ED   | 854.000   |
|                             | 0102-115-    | TYPE III BARRICADE                                                                   | ED   | 1,914.000 |
|                             | 0102-913- 21 | REMOVABLE TAPE, WHITE, SOLID 6"                                                      | GM   | 0.283     |
|                             | 0102-913- 31 | REMOVABLE TAPE, YELLOW, SOLID, 6"                                                    | GM   | 0.243     |
|                             | 0107- 1-     | LITTER REMOVAL                                                                       | AC   | 1.020     |
|                             | 0108- 2-     | MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44924315201)                      | LS   | 1.000     |
|                             | 0327- 70- 4  | MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH                                      | SY   | 92.000    |
|                             | 0327- 70- 5  | MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH                                      | SY   | 62.000    |
|                             | 0327- 70- 7  | MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH                                      | SY   | 7.000     |
|                             | 0327- 70- 12 | MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH                                  | SY   | 2,408.000 |
|                             | 0337- 7- 82  | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22                        | TN   | 189.100   |
|                             | 0999- 16-    | PARTNERING, DO NOT BID (44924315201)                                                 | LS   | 1.000     |
|                             | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44924315201)                                 | LS   | 1.000     |
| <b>Section 0003 Signing</b> |              |                                                                                      |      |           |
|                             | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                                       | EA   | 79.000    |
|                             | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44924315201)                               | LS   | 1.000     |
|                             | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT              | LF   | 8.000     |
|                             | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK               | LF   | 33.000    |
|                             | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"         | GM   | 0.015     |
|                             | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW                                                | EA   | 2.000     |
|                             | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON                  | LF   | 84.000    |
|                             | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"                             | GM   | 0.140     |
|                             | 0711- 16-131 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP | GM   | 0.142     |
|                             | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"                            | GM   | 0.114     |