

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	04250905	Call Order: 003	Proposal: E4Y06	District:04
Counties:	BROWARD			
Road Name:	SR-A1A FROM FLAMINGO AVENUE TO SOUTH OF PINE AVE - RES			
Limits:	86050000			
Project(s):	44840515201(*)	Federal Aid No: N/A		
Project(s):	44840515202	Federal Aid No: N/A		
Project(s):	44840515203	Federal Aid No: N/A		
Total Roadway Length:	5.577 Miles	Contract Days:	224	
Total Bridge Length:	0.000 Miles	Letting Date:	09/05/25	
Total Proposal Length:	5.577 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45	
Proposal Budget Estimate:	\$2,865,730.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, MOT (standard, traffic control officer, pedestrian LCD, signalization, traffic detection, barricade), protections (sediment, inlet), earthwork (borrow excavation, excavation), asphalt (milling, resurfacing), concrete (removal, curb and gutter, sidewalk, driveways, prestressed pole), pavement markings (detectable, RPM, painted, thermoplastic, bike lane, patterned, mid-block crossing), pavers, signing (single-column, tubular marker), signalization (signal cable, aluminum pole pedestal, aluminum pole remove, auxiliaries, pedestrian signal and detection), pull/splice box, conduit, electrical service (overhead, underground, wire, disconnect), utilities adjustments (manhole, valve box, meter box), tree (protection, pruning), and sod along State Road A1A (North Ocean Drive) from south of Flamingo Avenue to south of Pine Avenue for 1.015 miles in the City of Fort Lauderdale and the Town of Lauderdale-by-the-Sea, Broward County.

PRE-QUALIFIED: Contractor must be pre-qualified.

PERMITS LINK:

PERFORMANCE BOND: A Contract / Performance bond is required for this project.

COMMERCIAL GENERAL LIABILITY INSURANCE:

The limits of coverage shall not be less than \$1,000,000 for each occurrence and not less than a \$5,000,000 annual general aggregate, inclusive of amounts provided by an umbrella or excess policy. The limits of coverage described herein shall apply fully to the work or operations performed under the Contract, and may not be shared with or diminished by claims unrelated to the contract. The policy/ies and coverage described herein may be subject to a deductible. Pay all deductibles as required by the policy. No policy/ies or coverage described herein may contain or be subject to a Retention or a Self-Insured Retention.

WORKERS COMPENSATION INSURANCE

SPECIAL NOTES:

- No rail involvement
- Include Special Provision SP0080307RDRB for Regional Dispute Review Board.
- Include Special Provision SP0080306 for Partnering for a lump sum of \$6,000.
- Include Special Provision SP0080303A for 45 Calander days for the acquisition of project material.
- Include LF (Town of Lauderdale by the Sea)
- Include MOA (Town of Lauderdale by the Sea)
- Include Proprietary Product (patterned pavement crosswalk)

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2025-26 (SECTION 7-13) FOR INSURANCE LIMITS.

Call Order: 003 Proposal: E4Y06

Call Order: 003 Proposal: E4Y06

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44840515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44840515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	164.000
	0102- 60-	WORK ZONE SIGN	ED	7,526.000
	0102- 61-	BUSINESS SIGN	EA	9.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	25,808.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	67,130.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	275.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	839.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,344.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,344.000
	0102-115-	TYPE III BARRICADE	ED	258.000
	0104- 10- 3	SEDIMENT BARRIER	LF	850.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	40.000
	0107- 1-	LITTER REMOVAL	AC	14.740
	0107- 2-	MOWING	AC	1.350
	0110- 1- 1	CLEARING & GRUBBING (44840515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,269.000
	0110- 21-	TREE PROTECTION BARRIER	LF	132.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	7.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	181.200
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44840515201)	LS	1.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	584.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	24,945.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	40.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,808.100
	0425- 5-	MANHOLE, ADJUST	EA	43.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	972.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	366.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,094.000
	0523- 3-	PATTERNED PAVEMENT	SY	796.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	26.000
	0527- 2-	DETECTABLE WARNINGS	SF	394.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	79.000
	0999- 16-	PARTNERING, DO NOT BID (44840515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44840515201)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (44840515202)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	32.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	15.000

Call Order: 003 Proposal: E4Y06

ALT	Item	Description	Unit	Quantity
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	4.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	21.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	568.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	11.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44840515201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.094
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,151.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	393.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	328.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.066
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	20.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	60.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	242.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.069
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	410.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	43.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.306
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.114
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.871
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.736
	0714- 10-	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	253.000
Section 0003 Lighting				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	17.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	341.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,238.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	78.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	3.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	690.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	5.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	5.000

Call Order: 003 Proposal: E4Y06

ALT	Item	Description	Unit	Quantity
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	28.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	10.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	40.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	22.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	6.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	20.000
	0654- 1- 20	MIDBLOCK CROSSWALK: IN ROADWAY LIGHT ASSEMBLY, FURNISH & INSTALL- SOLAR POWERED, COMPLETE CROSSING	AS	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	34.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	20.000
Section 0005 Utilities				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	2.000
	0425- 6-	VALVE BOXES, ADJUST	EA	46.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (44840515203)	LS	1.000
	1080- 21-300	UTILITY FIXTURE, VALVE/METER BOX, INSTALL- BOX FURNISHED BY UTILITY	EA	18.000