

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04260403 Call Order: 002 Proposal: E4W06 District:04

Counties: PALM BEACH

Road Name: SR-811/ALT A1A OVER LOXAHATCHEE RIVER BRIDGE 930339

Limits: 93090000

Project(s): 44386725201(*)

Federal Aid No: N/A

Total Roadway Length:	0.219 Miles	Contract Days:	150
Total Bridge Length:	0.218 Miles	Letting Date:	04/03/26
Total Proposal Length:	0.437 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$1,677,012.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of but are not limited to, MOT (standard, barrier-mounted work zone sign, ped LCD, arrow board, PCMS), monitor structures (inspection, settlement), protections (turbidity barrier), bridge fender system (remove, plastic marine lumber), structures rehab (spall repair, crack injection, crack seal), pile (prestressed, splice, wrap cluster), navigation lights (fixed bridge), along State Road 811 (Alt A1A) over Loxahatchee River Bridge No. 930339 for 0.219 miles in the City of Jupiter, Palm Beach County.

- PRE-QUALIFIED: Contractor must be pre-qualified.
- PERFORMANCE BOND: A Contract / Performance bond is required for this project.
- COMMERCIAL GENERAL LIABILITY INSURANCE:
- INSURANCE REQUIRED FOR CONSTRUCTION AT RAILROADS:
- WORKERS COMPENSATION INSURANCE

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2025-26 (SECTION 7-13) FOR INSURANCE LIMITS.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 002 Proposal: E4W06

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 71- 1	BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL	LF	257.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	13.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	1.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	53.000
	0455- 17-114	PRE-PLANNED PILE SPLICE, CONCRETE SQUARE, 14"	EA	14.000
	0455- 34- 2	PRESTRESSED CONCRETE PILING, 14" SQ.	LF	262.000
	0455- 76-	WRAP PILE CLUSTERS	EA	136.000
	0471- 1- 1	FENDER SYSTEM,PLASTIC MARINE LUMBER,REINFORCED	MB	8.600
	0471- 1- 2	FENDER SYSTEM,PLASTIC MARINE LUMBER, NON-REINFORCED	MB	2.500
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (44386725201)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44386725201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44386725201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,100.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	900.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	22,162.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,800.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	150.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	328.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	752.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44386725201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44386725201)	LS	1.000