

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	04260206	Call Order: 002	Proposal: E4Y07	District:04
Counties:	PALM BEACH			
Road Name:	- ROAD/SLOPE PROTECTION			
Limits:	93140000			
Project(s):	45538715201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.140 Miles	Contract Days:	112	
Total Bridge Length:	0.000 Miles	Letting Date:	02/06/26	
Total Proposal Length:	0.140 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45	

Proposal Budget Estimate: \$2,739,575.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, MOT (detour, traffic control officer, barricade, PCMS), protections (sediment, turbidity), monitor structures (inspection, settlement, vibration), earthwork (excavation, embankment), asphalt (milling, resurfacing, reconstruction), concrete (removal), rip-rap (rubble), bedding stone, guardrail (deep post, steel), pavement markings (rumble strips, RPM, painted, thermoplastic) along State Road 700, for a total of 0.14 miles in Palm Beach County.

•PRE-QUALIFIED: Contractor must be pre-qualified.

•PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2025-26 (SECTION 7-13) FOR INSURANCE LIMITS.

Call Order: 002 Proposal: E4Y07

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45538715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45538715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	640.000
	0102- 60-	WORK ZONE SIGN	ED	3,808.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,016.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	504.000
	0102-115-	TYPE III BARRICADE	ED	1,344.000
	0104- 10- 3	SEDIMENT BARRIER	LF	796.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,191.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	5.350
	0107- 2-	MOWING	AC	1.580
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (45538715201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (45538715201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45538715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	16.000

Call Order: 002 Proposal: E4Y07

ALT	Item	Description	Unit	Quantity
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (45538715201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	327.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	2,007.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	141.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	3,138.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	63.300
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	254.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	33.200
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	1,955.900
	0530- 74-	BEDDING STONE	TN	7,557.900
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	673.000
	0536- 7- 1	SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK CONDITION- TIMBER OR STEEL	EA	122.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	673.000
	0999- 16-	PARTNERING, DO NOT BID (45538715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45538715201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	0.497
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	48.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45538715201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.332
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.224
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.108
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.024