

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 04260306 Call Order: 002 Proposal: E4X96 District:04

Counties: ST LUCIE

Road Name: SR-9/I-95 FROM SOUTH OF BECKER RD TO SOUTH OF GATLIN BLVD

Limits: 94001030

Project(s): 45536517201(\*)

Federal Aid No: N/A

Total Roadway Length:	5.070 Miles	Contract Days:	95
Total Bridge Length:	0.000 Miles	Letting Date:	03/06/26
Total Proposal Length:	5.070 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	45

Proposal Budget Estimate: \$5,600,000.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of, but are not limited to, MOT (standard, traffic control officer, arrow board, PCMS, barricade, portable regulatory, radar speed display), protections (floating turbidity, inlet), asphalt (milling, resurfacing), signing (single-column F&I, single-column remove, sign strip), pavement markings (RPM, painted, thermoplastic), and weigh-in-motion (MCSAW), along State Road 9 (I-95) from Becker Road to Gatlin Boulevard for 5.070 miles in the City of Port St. Lucie, St. Lucie County.

**BUDGETARY CONSTRAINTS**

For the purpose of bidding, the Department has established a maximum budget of \$5,600,000.00. This amount is not the Department's official cost estimate for the work but is the budgetary constraint established for this Contract. Submission of a bid under the maximum budget is not a guarantee of Contract Award and cannot be interpreted as an appropriate or awardable bid amount. For this Contract, the Department will reject as non-responsive any bid in which the Bidder submits a bid in excess of the maximum budget amount shown above.

During preparation of the bid, if concerns regarding the Department's maximum budget arise, submit a letter of budget concern to District Maintenance Contracts Administrator by February 16, 2026. The Department will review the letter of budget concern and determine its next course of action. This process is established to provide the opportunity for bid proposal holders for this Contract to express budget constraint issues prior to submission of a bid.

PRE-QUALIFIED Contractor must be pre-qualified.

PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2025-26 (SECTION 7-13) FOR INSURANCE LIMITS.

**Call Order: 002 Proposal: E4X96**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	950.000
	0102- 60-	WORK ZONE SIGN	ED	3,234.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,053.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	142.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	283.000
	0102-115-	TYPE III BARRICADE	ED	110.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	214.000

**Call Order: 002 Proposal: E4X96**

ALT	Item	Description	Unit	Quantity
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	214.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	760.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	88.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	199,305.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	15,215.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	10,662.800
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	1,046.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	9.588
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.933
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	442.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,431.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	85.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	17.674
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	30.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	25.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	9.324
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	220.000
	0924-102-	WORK ZONE COLLISION DETECTION AND AVOIDANCE SYSTEM FOR PAVING OPERATIONS	LS	1.000
	0999- 16-	PARTNERING, DO NOT BID	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	8.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	3.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	8.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,063.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	442.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,431.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	85.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000

**Call Order: 002 Proposal: E4X96**

ALT	Item	Description	Unit	Quantity
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	44.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	25.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	220.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	382.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	8.568
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.886
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	17.310
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	8.568
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.958
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.047
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.364
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.756
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	52.000
<b>Section 0003 Signalization</b>				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	95.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	1.000
<b>Section 0004 Architectural</b>				
	0770- 4- 15	MCSAW, WEIGHING, FURNISH AND INSTALL	EA	1.000