

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04260306 Call Order: 004 Proposal: E4Y40-R0 District:04
Counties: BROWARD
Road Name: BROWARD NPDES CORRECTIVE ACTIONS
Limits: Midpoint
Project(s): 42833377201(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: 365
Total Bridge Length: 0.000 Miles Letting Date: 03/06/26
Total Proposal Length: 0.000 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 13
Proposal Budget Estimate: \$450,000.00

Please read the full advertisement

Description:

The work under this Contract consists of resolving maintenance issues related to the State's drainage system and to providing corrective actions for National Pollution Elimination Discharge Systems (NPDES)-related inspection deficiencies to assets servicing the State Road System throughout Broward County.

ADVERTISED ESTIMATE The award amount and contract performance bond shall be based on the Department's advertised estimate amount of \$450,000.00 and not the contractor's bid total.

PERFORMANCE BOND A Contract / Performance bond is required for this project.

REQUIRED SUBMITTAL WITH BID: Drainage Repair Experience Form Number 854-070-05

WORKERS COMPENSATION INSURANCE

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2025-26 (SECTION 7-13) FOR INSURANCE LIMITS.

Call Order: 004 Proposal: E4Y40-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	68.000
	0120- 1-	REGULAR EXCAVATION	CY	220.000
	0120- 4-	SUBSOIL EXCAVATION	CY	1.000
	0120- 6-	EMBANKMENT	CY	60.000
	0120- 10- 21	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH UP TO 15'	LF	3,500.000
	0120- 10- 22	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH 15-30'	LF	3,000.000
	0121- 70-	FLOWABLE FILL	CY	160.000
	0173- 77- 1	SUBSURFACE PRESSURE GROUTING, SAND CEMENT	CY	10.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	20.000
	0350- 6-	CLEANING & SEALING RANDOM CRACKS- CONCRETE PAVEMENT	LF	100.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	20.000
	0425- 4-	INLETS, ADJUST	EA	5.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000
	0425- 82-	REPLACE GRATE	EA	10.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	18.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	18.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	18.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	3.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	3.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	30.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	30.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	30.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	60.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	4.000
	E107- 1- 1	LITTER REMOVAL	AC	23.000
	E110- 2-	CLEARING & GRUBBING	AC	2.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	528.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	225.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	10.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	1.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	1,350.000
	E425- 73- 6	SECURE MANHOLE / INLET LIDS	EA	50.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	1,200.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	450.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	200.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	200.000
	E524- 1- 1	CONCRETE DITCH PAVEMENT REPAIR	CY	2.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	10,000.000
	E575- 1- 8	SODDING, BAHIA	SY	5,000.000
	E577- 70-	SHOULDER REWORK	SY	5,000.000