

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	04261106	Call Order: 003	Proposal: E4Y97-R0	District:04
Counties:	BROWARD			
Road Name:	BROWARD COUNTY DESILTING			
Limits:	Midpoint			
Project(s):	45341127201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	11/06/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$350,000.00

Please read the full advertisement

Description:

The work under this Contract consists of providing all labor, equipment, material, and incidentals necessary for the cleaning, evaluating, repairing the drainage systems on State Roadways in Broward County, and collecting the associated video and Geographic Information system (GIS) data.

ADVERTISED ESTIMATE: The award amount and contract performance bond shall be based on the Department s advertised estimate amount of \$350,000.00 and not the contractor s bid total.

PRE-QUALIFIED: Contractor does not need to be pre-qualified.

PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION
FY 2026-27 (SECTION 7-13) FOR INSURANCE LIMITS.

Call Order: 003 Proposal: E4Y97-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	40.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	2.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	4.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	2,100.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	8,000.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	5,000.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	1,500.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	300.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	100.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	36.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	36.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	24.000
	E431- 1- 24	PIPE LINER, CURED IN PLACE, 49-60"	LF	24.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	2,500.000
	E999- 3- 1	HYDRAULIC PUMP, 4"	HR	16.000
	E999- 3- 2	HYDRAULIC PUMP, 6"	HR	8.000