

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	04261106	Call Order: 005	Proposal: E4Z04-R0	District:04
Counties:	PALM BEACH			
Road Name:	PALM BEACH COUNTY DRAINAGE REPAIRS			
Limits:	Midpoint			
Project(s):	45733717201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	11/06/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$200,000.00

Please read the full advertisement

Description:

The work under this contract consists of supplying all equipment, materials, labor and incidentals necessary to clean, video and repair leaks in the drainage system on state roads in Palm Beach County.

ADVERTISED ESTIMATE: The award amount and contract performance bond shall be based on the Department s advertised estimate amount of \$200,000.00 and not the contractor s bid total.

PRE-QUALIFIED: Contractor does not need to be pre-qualified.

PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2026-27 (SECTION 7-13) FOR INSURANCE LIMITS.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 005 Proposal: E4Z04-R0				
ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	10.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	10.000
	0430-821- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" STORM SEWER	EA	10.000
	0430-821- 38	CLEANING & SEALING EXISTING PIPE JOINT, 36" STORM SEWER	EA	10.000
	0430-821- 42	CLEANING & SEALING EXISTING PIPE JOINT, 54", STORM SEWER	EA	10.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	30.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	20.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	5.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	100.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	10,000.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	3,000.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	800.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	600.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	200.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	100.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	100.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	14,000.000