

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

|                        |                                                       |                            |                 |             |
|------------------------|-------------------------------------------------------|----------------------------|-----------------|-------------|
| Letting:               | 04261009                                              | Call Order: 001            | Proposal: E4Y18 | District:04 |
| Counties:              | PALM BEACH                                            |                            |                 |             |
| Road Name:             | SR-802/LAKE WORTH RD FR EVERETT COURT TO E OF ERIE ST |                            |                 |             |
| Limits:                | 93180000                                              |                            |                 |             |
| Project(s):            | 44981015201(*)                                        | Federal Aid No: N/A        |                 |             |
| Total Roadway Length:  | 0.964 Miles                                           | Contract Days:             | 169             |             |
| Total Bridge Length:   | 0.000 Miles                                           | Letting Date:              | 10/09/26        |             |
| Total Proposal Length: | 0.964 Miles                                           | Contract Execution Days:   | 10              |             |
|                        |                                                       | Special Start Date:        | N/A             |             |
|                        |                                                       | Aquis/Flexible Start Time: | 60              |             |

Proposal Budget Estimate: \$2,012,133.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of, but are not limited to, MOT (standard, traffic control officer, barrier, arrow board, PCMS, signalization, traffic detection, barricade), monitor structures (inspection, settlement), earthwork (excavation, embankment), concrete (removal, curb/gutter, curb, sidewalk, driveways, prestressed pole), aluminum (handrail/guiderail, signal pole, signal pole remove), asphalt (base, milling, resurfacing), pavement markings (detectable, painted, thermoplastic, bike lane), signing (single-column, multi-column, sign strip, enhanced assembly-solar, tubular marker, object marker, RPM), signalization (signal cable, auxiliaries F&I, ped signal, ped signal remove, ped detector, ped detector remove, cabinet modify, loop assembly), pull/splice box, conduit, electrical service (power, wire), utilities adjustments (manhole), tree (protection), and sod along State Road 802 (Lake Worth Beach Road) from Everett Court to Erie Street, for 0.482 miles in the City of Lake Worth Beach, and within unincorporated portions of, Palm Beach County.

- PRE-QUALIFIED: Contractor must be pre-qualified.
- PERFORMANCE BOND: A Contract / Performance bond is required for this project.

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2026-27 (SECTION 7-13) FOR INSURANCE LIMITS

**Call Order: 001 Proposal: E4Y18**

| ALT                         | Item         | Description                                                            | Unit | Quantity   |
|-----------------------------|--------------|------------------------------------------------------------------------|------|------------|
| <b>Section 0001 Roadway</b> |              |                                                                        |      |            |
|                             | 0101- 1-     | MOBILIZATION (44981015201)                                             | LS   | 1.000      |
|                             | 0102- 1-     | MAINTENANCE OF TRAFFIC (44981015201)                                   | LS   | 1.000      |
|                             | 0102- 14-    | TRAFFIC CONTROL OFFICER                                                | HR   | 76.000     |
|                             | 0102- 60-    | WORK ZONE SIGN                                                         | ED   | 2,547.000  |
|                             | 0102- 71- 13 | TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE                          | LF   | 2,515.000  |
|                             | 0102- 71- 23 | TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE                      | LF   | 238.000    |
|                             | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                 | ED   | 21,722.000 |
|                             | 0102- 74- 8  | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | FD   | 834.000    |
|                             | 0102- 76-    | ARROW BOARD / ADVANCE WARNING ARROW PANEL                              | ED   | 198.000    |
|                             | 0102- 99-    | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                            | ED   | 226.000    |
|                             | 0102-104-    | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION                  | ED   | 338.000    |
|                             | 0102-107- 1  | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION              | ED   | 338.000    |

**Call Order: 001 Proposal: E4Y18**

| ALT                         | Item         | Description                                                                     | Unit | Quantity   |
|-----------------------------|--------------|---------------------------------------------------------------------------------|------|------------|
|                             | 0102-115-    | TYPE III BARRICADE                                                              | ED   | 232.000    |
|                             | 0104- 18-    | INLET PROTECTION SYSTEM                                                         | EA   | 18.000     |
|                             | 0107- 1-     | LITTER REMOVAL                                                                  | AC   | 15.920     |
|                             | 0107- 2-     | MOWING                                                                          | AC   | 12.200     |
|                             | 0108- 1-     | MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44981015201) | LS   | 1.000      |
|                             | 0110- 1- 1   | CLEARING & GRUBBING (44981015201)                                               | LS   | 1.000      |
|                             | 0110- 4- 10  | REMOVAL OF EXISTING CONCRETE                                                    | SY   | 1,324.000  |
|                             | 0110- 21-    | TREE PROTECTION BARRIER                                                         | LF   | 98.000     |
|                             | 0120- 1-     | REGULAR EXCAVATION                                                              | CY   | 316.600    |
|                             | 0120- 6-     | EMBANKMENT                                                                      | CY   | 43.600     |
|                             | 0285-715-    | OPTIONAL BASE, BASE GROUP 15                                                    | SY   | 556.000    |
|                             | 0327- 70- 6  | MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH                             | SY   | 20,827.000 |
|                             | 0334- 1- 13  | SUPERPAVE ASPHALTIC CONC, TRAFFIC C                                             | TN   | 54.900     |
|                             | 0337- 7- 83  | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76 -22                 | TN   | 1,751.200  |
|                             | 0425- 5-     | MANHOLE, ADJUST                                                                 | EA   | 14.000     |
|                             | 0515- 1- 2   | PIPE HANDRAIL - GUIDERAIL, ALUMINUM                                             | LF   | 8.000      |
|                             | 0520- 1- 10  | CONCRETE CURB & GUTTER, TYPE F                                                  | LF   | 503.000    |
|                             | 0520- 2- 4   | CONCRETE CURB, TYPE D                                                           | LF   | 2,279.000  |
|                             | 0522- 1-     | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK                                       | SY   | 393.000    |
|                             | 0522- 2-     | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK                                       | SY   | 541.000    |
|                             | 0527- 2-     | DETECTABLE WARNINGS                                                             | SF   | 264.000    |
|                             | 0570- 1- 2   | PERFORMANCE TURF, SOD                                                           | SY   | 2,562.000  |
|                             | 0710- 11-160 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL                   | EA   | 2.000      |
|                             | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS                              | EA   | 2.000      |
|                             | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"                          | GM   | 0.444      |
|                             | 0999- 16-    | PARTNERING, DO NOT BID (44981015201)                                            | LS   | 1.000      |
|                             | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44981015201)                            | LS   | 1.000      |
| <b>Section 0002 Signing</b> |              |                                                                                 |      |            |
|                             | 0700- 1-111  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF           | EA   | 15.000     |
|                             | 0700- 1-112  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF              | EA   | 7.000      |
|                             | 0700- 1-113  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF              | EA   | 4.000      |
|                             | 0700- 1-600  | SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE                                      | EA   | 23.000     |
|                             | 0700- 2-113  | MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF               | EA   | 1.000      |
|                             | 0700- 2-114  | MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF               | EA   | 1.000      |
|                             | 0700- 2-600  | MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE                                       | EA   | 1.000      |
|                             | 0700- 13- 15 | RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'                             | EA   | 10.000     |
|                             | 0700-142-802 | ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, RELOCATE - GROUND MOUNT          | EA   | 1.000      |
|                             | 0704- 1- 4   | TUBULAR MARKER, 36" YELLOW POST                                                 | EA   | 12.000     |
|                             | 0705- 10- 1  | OBJECT MARKER, TYPE 1                                                           | EA   | 3.000      |

**Call Order: 001 Proposal: E4Y18**

| ALT                               | Item         | Description                                                                                            | Unit | Quantity  |
|-----------------------------------|--------------|--------------------------------------------------------------------------------------------------------|------|-----------|
|                                   | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                                                         | EA   | 293.000   |
|                                   | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44981015201)                                                 | LS   | 1.000     |
|                                   | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT                                | LF   | 1,607.000 |
|                                   | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK                                 | LF   | 349.000   |
|                                   | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"                           | GM   | 0.746     |
|                                   | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL                                                      | EA   | 4.000     |
|                                   | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW                                                                  | EA   | 36.000    |
|                                   | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON                                    | LF   | 82.000    |
|                                   | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"                 | GM   | 0.163     |
|                                   | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK                                              | LF   | 776.000   |
|                                   | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE                                                               | EA   | 17.000    |
|                                   | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW                                                                 | EA   | 17.000    |
|                                   | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"                                               | GM   | 1.064     |
|                                   | 0711- 16-102 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"                                               | GM   | 0.037     |
|                                   | 0711- 16-131 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP                    | GM   | 0.791     |
|                                   | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"                                              | GM   | 0.925     |
|                                   | 0714- 10-    | GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE                                                             | SF   | 926.000   |
| <b>Section 0003 Signalization</b> |              |                                                                                                        |      |           |
|                                   | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE                                                           | LF   | 877.000   |
|                                   | 0632- 7- 1   | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL                                     | PI   | 2.000     |
|                                   | 0632- 7- 6   | SIGNAL CABLE, REMOVE- INTERSECTION                                                                     | PI   | 2.000     |
|                                   | 0635- 2- 14  | PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE                                                           | EA   | 40.000    |
|                                   | 0639- 1-122  | ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR                              | AS   | 2.000     |
|                                   | 0639- 2- 1   | ELECTRICAL SERVICE WIRE, FURNISH & INSTALL                                                             | LF   | 167.000   |
|                                   | 0641- 2- 12  | PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE                                                 | EA   | 2.000     |
|                                   | 0641- 2- 60  | PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE                                | EA   | 1.000     |
|                                   | 0646- 1- 11  | ALUMINUM SIGNALS POLE, PEDESTAL                                                                        | EA   | 15.000    |
|                                   | 0646- 1- 60  | ALUMINUM SIGNALS POLE, REMOVE                                                                          | EA   | 2.000     |
|                                   | 0650- 2-109  | VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED | EA   | 17.000    |
|                                   | 0653- 1- 11  | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY                                              | AS   | 14.000    |
|                                   | 0653- 1- 12  | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS                                             | AS   | 1.000     |
|                                   | 0653- 1- 60  | PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN                                          | AS   | 6.000     |
|                                   | 0660- 2-106  | LOOP ASSEMBLY, F&I, TYPE F                                                                             | AS   | 20.000    |
|                                   | 0665- 1- 11  | PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD                                                       | EA   | 16.000    |

**Call Order: 001 Proposal: E4Y18**

| ALT | Item        | Description                                          | Unit | Quantity |
|-----|-------------|------------------------------------------------------|------|----------|
|     | 0665- 1- 60 | PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN | EA   | 12.000   |
|     | 0676- 1-500 | TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY     | EA   | 2.000    |