

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	04261009	Call Order: 003	Proposal: E4Y77-R0	District:04
Counties:	DIST/ST-WIDE			
Road Name:	D/W STRUCTURES REPAIRS PUSHBUTTON-ANCILLARIES - ROUTINE MAINTENANCE			
Limits:	Midpoint			
Project(s):	44476877201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	10/09/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$275,000.00

Please read the full advertisement

Description:

The work under this Contract consists of a Work Document driven contract to perform routine and priority repairs on ancillary structures including but not limited to, traffic signal mast arms and sign structure repairs, coating of existing structural steel, bolt replacement, bolt tightening, grout pad replacement, and other miscellaneous concrete and steel repairs at various locations throughout District 4.

ADVERTISED ESTIMATE: The award amount and contract performance bond shall be based on the Department s advertised estimate amount of \$275,000.00 and not the contractor s bid total.

- PERFORMANCE BOND: A Contract / Performance bond is required for this project.
- REQUIRED SUBMITTAL WITH BID: Experience Form Traffic Signal Repair 850-070-07

PLEASE READ STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION FY 2026-27 (SECTION 7-13) FOR INSURANCE LIMITS.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 003 Proposal: E4Y77-R0

ALT	Item	Description	Unit	Quantity
Section 0001 TRAFFIC CONTROL DEVICES CONTROL (MH)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	20.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	20.000
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	2.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	2.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	2.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	4.000
	0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES	LB	495.000
	0460- 94-	STRUCTURAL STEEL REPAIR- WELDS	LF	4.000
	0561- 2-	COATING EXISTING STRUCTURAL STEEL	SF	250.000
	0649- 26- 1	STEEL MAST ARM ASSEMBLY, REMOVE, POLE ONLY- ENTIRE FOUNDATION REMAINS	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0649- 26- 7	STEEL MAST ARM ASSEMBLY, REMOVE, REMOVE ARM AND ATTACHMENTS; POLE REMAINS	EA	1.000
	0649- 40- 1	STEEL MAST ARM ASSEMBLY- REPLACE SCREEN ON EXISTING POLE	EA	30.000
	0649- 40- 2	STEEL MAST ARM ASSEMBLY- REPLACE HAND HOLE COVER ON EXISTING POLE	EA	1.000
	0649- 40- 3	STEEL MAST ARM ASSEMBLY- REPLACE POLE CAP ON EXISTING POLE	EA	10.000
	0649- 40- 4	STEEL MAST ARM ASSEMBLY- REPLACE STRUCTURAL GROUT PAD ON EXISTING POLE	EA	30.000
	0649- 40- 5	STEEL MAST ARM ASSEMBLY- REPAIR/REPLACE BROKEN WELD ON EXISTING POLE	EA	1.000
	0649- 40- 8	STEEL MAST ARM ASSEMBLY- FURNISH & INSTALL BIRD SCREEN ON EXISTING POLE	EA	15.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	1.000
	0700- 4-621	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, SPAN	EA	1.000
	0715- 19- 61	HIGH MAST LIGHT POLE, REMOVE POLE- FOUNDATION REMAINS	EA	1.000
	0715- 19- 62	HIGH MAST LIGHT POLE, SHALLOW FOUNDATION REMOVAL	EA	1.000
	E101- 72-	MOBILIZATION (EMERGENCY RESPONSE)	EA	1.000
	E460- 82-	BOLT TIGHTENING	EA	300.000