## Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 05181204 Call Order: 005 Proposal: E5U97 District:05

Counties: LAKE

Road Name: Asphalt Mill and Resurface on SR 25 (US 27)

Limits: Midpoint

Project(s): 42915717215(\*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 110

Total Bridge Length: 0.000 Miles Letting Date: 12/04/18

Total Proposal Length: 0.000 Miles Contract Execution Days:

Special Start Date: N/A

Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$982,615.00

Please read the full advertisement

Description:

FDOT DISTRICT 5 Proposal ID No.: E5U97

Financial Project No.: 429157-1-72-15

Fiscal Year: 2019 County: Lake Calendar Days: 110 Lead Time: 14 days

This is a Maintenance Pay Item Contract.

## Intent:

The work under this Contract consist of milling and resurfacing asphalt roadway pavement, modification of a median opening, installation of thermoplastic pavement markings and RPMs on SR 25 (US 27) and the installation of an over-lane sign, attached to Bridge # 110093 on SR 50 in Lake County.

## Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of asphalt paving projects, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Hot Plant Mix Bituminous Course" will suffice to meet the above requirements.

Call Order: 005 Proposal: E5U97

ALT Item	Description	Unit	Quantity
Section 0001 ASPHALT	REPAIR (MECHANICAL) (TN)		
0101- 1-	MOBILIZATION	LS	1.000
0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
0110- 1- 1	CLEARING & GRUBBING	LS	1.000
0110- 4-10	REMOVAL OF EXISTING CONCRETE	SY	47.000
0120- 1-	REGULAR EXCAVATION	CY	3.000
0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	76.000
0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	34.000
0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	105,000.000
0334- 1-13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5.700
0337- 7-82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	5,800.000
0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	562.000
0520- 2- 2	CONCRETE CURB, TYPE B	LF	94.000
0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	121.000
0570- 1- 2	PERFORMANCE TURF, SOD	SY	149.000
0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	12.000
0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000
0700- 1-11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
0700- 1-12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
0700- 1-50	SINGLE POST SIGN, RELOCATE	AS	1.000
0700- 1-60	SINGLE POST SIGN, REMOVE	AS	2.000
0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	1.000
0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
0700- 4-140	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, OVERPASS BRIDGE MOUNT	EA	1.000
0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	4.000
0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	1,144.000
0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.000
0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,665.000
0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,641.000
0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	279.000
0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	108.000
0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2,422.000
0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.534
0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.276
0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	6.750
0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.598
0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, $8"$	GM	0.263
0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.200