Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 05181002 Call Order: 005 Proposal: E5U77 District:05

Counties: VOLUSIA

Road Name: DRAINAGE MAINTENANCE AND REPAIR

Limits: Midpoint

Project(s): 42798617215(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	180
Total Bridge Length:	0.000 Miles	Letting Date:	10/02/18
Total Proposal Length:	0.000 Miles	Contract Execution Days:	
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: $2,155,958.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID: E5U77
Project No: 427986-1-72-15
Fiscal Year: 2019
County: Volusia
Contract Calendar Days: 180
Lead Time: 14 Days

This is a Maintenance, Pay Item Project.

INTENT AND SCOPE: The work in this project includes desilting stormwater pipes and structures, storm water pipe lining, and drainage structures repairs in locations on SR 5 (US 1), SR 400, SR 441, & SR 442.

This project involves encroachment of railroad rights of way. Enhanced insurance limits and other considerations are specified in the contract documents.

EXPERTISE REQUIRED:
For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of
prequalification with the Department in "Drainage" will suffice to meet the above requirements.

Call Order: 005 Proposal: E5U77

ALT	Item	Description	Unit	Quantity
Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0110- 8- 2	UNDERWATER DEBRIS REMOVAL	LF	40.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	7,582.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	8,263.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	2,947.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	285.000
	0431- 1- 1	PIPE LINER, OPTIONAL MATERIAL, 0-24"	LF	7,852.000
	0431- 1- 2	PIPE LINER, OPTIONAL MATERIAL, 25-36"	LF	8,263.000
	0431- 1- 3	PIPE LINER, OPTIONAL MATERIAL, 37-48"	LF	2,947.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	107.000