

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 05181002      Call Order: 009      Proposal: E5Z52      District:05

Counties: LAKE

Road Name: SR 40 OVER ST JOHNS RIVER BRIDGE # 110077

Limits: 11140000

Project(s): 44116715201(\*)

Federal Aid No: N/A

Total Roadway Length:	0.098 Miles	Contract Days:	100
Total Bridge Length:	0.098 Miles	Letting Date:	10/02/18
Total Proposal Length:	0.196 Miles	Contract Execution Days:	
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120

Proposal Budget Estimate: \$311,983.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of the removal and replacement of the drag net style traffic barrier with a semaphore type resistance barrier and maintenance platform on a new foundation on SR 40 over St. Johns River Bridge No. 110077 in Lake County, FL.

**Call Order: 009 Proposal: E5Z52**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	3.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	14.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	336.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	2,608.000
	0455- 88- 5	DRILLED SHAFT, 48" DIA	LF	47.000
	0455-107- 5	DRILLED SHAFT CASING, 48" DIAMETER	LF	47.000
	0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES	LB	270.000
	0508- 2- 1	MOVABLE BRIDGE GATE, F&I	AS	1.000
	0508- 2- 6	MOVABLE BRIDGE GATE, REMOVE & DISPOSE	AS	1.000
	0508- 4-	MOVABLE BRIDGE ELECTRICAL EQUIPMENT, REHABILITATION (44116715201)	LS	1.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	31.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44116715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44116715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	16.000
	0102- 60-	WORK ZONE SIGN	ED	752.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	168.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	840.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	56.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	40.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	94.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44116715201)	LS	1.000