

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05190402 Call Order: 003 Proposal: E5U86 District:05
Counties: VOLUSIA
Road Name: Asphalt Pavement Repair
Limits: Midpoint
Project(s): 44169417201(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: 90
Total Bridge Length: 0.000 Miles Letting Date: 04/02/19
Total Proposal Length: 0.000 Miles Contract Execution Days:
Special Start Date: N/A
Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$382,182.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID No. E5U86
Financial Project No. 441694-1-72-01
Fiscal Year 2019
County: Volusia
Contract Calendar Days:90
Lead Time: 14 Days

This is a Maintenance Pay Item Contract.

Intent:

Work under this contract consists of milling & resurfacing asphalt pavement and pavement markings installation in two locations of SR 44.

EXPERTISE REQUIRED:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Asphalt Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Hot Plant Mix Bituminous Course" will suffice to meet the above requirements.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 003 Proposal: E5U86

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	90.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	90.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	24,367.900
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	4,163.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	3,018.500
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	420.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	96.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	231.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	110.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	17.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	15.550
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	4.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	5,140.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	3,720.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	6,230.000