

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05190205 Call Order: 006 Proposal: E5U82 District:05

Counties: VOLUSIA

Road Name: Concrete Slab Replacement

Limits:

Project(s): 44168217201

Federal Aid No: N/A

Total Roadway Length:

0.000 Miles

Contract Days:

270

Total Bridge Length:

0.000 Miles

Letting Date:

02/05/19

Total Proposal Length:

0.000 Miles

Contract Execution Days:

10

Special Start Date:

N/A

Aquis/Flexible Start Time:

14

Proposal Budget Estimate:

\$1,739,542.00

Please read the full advertisement

Description:

FDOT District 5

Proposal ID: E5U82

Financial Project No: 441682-1-72-01

Fiscal Year: 2019

County: Volusia

Contract Calendar Days: 270

Lead Time: 14 Days

This is a Maintenance Pay Item Project.

INTENT AND SCOPE:

Concrete Slab Replacement on SR 5 (US 1) from Fleming Avenue to Reed Canal Road.

EXPERTISE REQUIRED:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Concrete Pavement Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Concrete Pavement Repair" will suffice to meet the above requirements.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 006 Proposal: E5U82

ALT	Item	Description	Unit	Quantity
Section 0001 CONCRETE PAVEMENT JOINT REPAIR (LF)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	130.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	7.000
	0104- 10- 3	SEDIMENT BARRIER	LF	100.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	40.000
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	11,412.000
	0350- 4- 5	REINFORCED CEMENT CONCRETE PAVEMENT,8"	SY	573.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT:	LF	25,772.000
	0350- 6-	CLEANING & SEALING RANDOM CRACKS- CONCRETE PAVEMENT	LF	220.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	11,349.000
	0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	2,530.400
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	22.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	80.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	45.000
	0570- 1- 1	PERFORMANCE TURF	SY	18.000
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	50.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	700.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	600.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	50.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	3.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	13.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	2,640.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	2,640.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	2,640.000